

Test Report

No B41-19-AI-I1

PRIME 1.4 Certification Tests Cases for Service Nodes

EQUIPMENT UNDER TEST	SINGLE-PHASE smart meter with integrated PRIME Power Line Communications
MODEL	AM170
FIRMWARE VERSION	01.04.03.01.0002
CERTIFICATION SCOPE	PRIME v1.4: Certification Process Profile: Electricity Meter with PRIME PHY and PRIME MAC. PRIME 1.4 CH1, CH5 • PRIME 1.4 PHY • PRIME 1.4 MAC layer ◦ Excluding security profiles ◦ Excluding backward compatibility • PRIME 1.4 Convergence layer
DATE OF EXECUTION	21st January to 5th March 2019

Responsible for tests	Smart Data & Protocol Laboratory Manager
	
Ibone García-Borreguero	Marta Castro



Author: Ibone García-Borreguero. Responsible for tests
Reviewer: Marta Castro. Smart Data & Protocol Laboratory Manager

NOTE: This test report shows the detailed information associated with the Test Report Summary no. B41-19-AI-I1 summary

TECNALIA, Parque Científico y Tecnológico de Gipuzkoa - Mikeletegi Pasalekua, 2. E-20009 Donostia-San Sebastián (Spain). All rights reserved.

This document contains confidential information that shall not be transmitted to any third party without written consent of TECNALIA. The same applies to file copying (including but not limited to electronic copies), wholly or partially.

It is prohibited to change any and all versions of this document in any manner whatsoever, including but not limited to dividing it into parts. In case of a conflict between an electronic version (e.g. PDF file) and the original paper version provided by TECNALIA, the latter will prevail.

TECNALIA and/or its associated companies disclaim liability for any direct, indirect, consequential or incidental damages that may result from the use of the information or data, or from the inability to use the information or data contained in this document.

INDEX

1.- EQUIPMENT UNDER TEST IDENTIFICATION.....	3
2.- SUMMARY OF TEST RESULTS FOR CHANNEL 1	5
3.- SUMMARY OF TEST RESULTS FOR CHANNEL 5	13
4.- APPLICANT	21
5.- PLACE OF RECEPTION AND EXECUTION OF THE TESTS	21
6.- STANDARDS AND TEST PROCEDURES EMPLOYED	21
7.- CONCLUSIONS	22
ANNEX I. TEST RESULTS.....	23
ANNEX II. MODIFICATIONS FROM PRIME 1.3.6 CERTIFIED MODEL AM170 TO CURRENT PRIME 1.4 MODEL MANUFACTURER/DEVELOPER DECLARATION	71

1.- EQUIPMENT UNDER TEST IDENTIFICATION

Unit:	SINGLE-PHASE smart meter with integrated PRIME Power Line Communications
Model:	AM170
Trade Mark:	ZPA Smart Energy a.s.
Serial Number:	M1: nº 18101760 (MAC 11:22:33:00:00:3C) M2: nº 18101761 (MAC 11:22:33:00:00:3D)
Manufacturer:	ZPA Smart Energy a.s.



The samples were selected and delivered by the applicant.

Equipment characteristics declared by the applicant:

Device type	ENERGY METER WITH PRIME COMMUNICATION
BaudRate	57600
Firmware version	01.04.03.01.0002
Applicable channel	Channels 1 and 5
Previous Tests	The board passed all the tests requested to be compliant with: EN 50065-1:2011 EN 50065-2-3:2003 + Ec:2003 + A1:2005 EN 50065-7:2001 at:

	Electronic Devices Laboratory of TECNALIA Test Report No. B41-18-AW-I1 for channel 1. See ANNEX II
Applicable tests	Profile Electricity Meter with PRIME PHY and PRIME MAC. PRIME 1.4 CH1, CH5 • PRIME 1.4 PHY • PRIME 1.4 MAC layer ○ Excluding security profiles ○ Excluding backwards compatibility • PRIME 1.4 Convergence layer

2.- SUMMARY OF TEST RESULTS FOR CHANNEL 1

Tools used for Certification

- Microchip Prime Manager Vendor Tool (VT) to configure the DUT, trigger actions, and confirm manually MAC and CL tests result. Also used as auxiliary SW to run some MAC and CL tests.
- Neuron Conformance Test Tool (NT) to run testcases defined in PRIME Certification 1.4 Service Node Test book v2.9.
- Tecnalia Testing Tool (TT) to run testcases defined in PRIME Certification 1.4 Service Node Test book v2.9.
- Tecnalia Lab. Auxiliary tools (LT) to run MAC and CL tests when needed and to check manually testcases to confirm final result.

PRIME 1.4 PHY Layer			Tools
2.5 PHY Test Cases: Transmission and reception test cases			
Type A Frame			
2.3.2.1	Verify error free reception of DBPSK type A frames in channel ch 1	PASS	TT
2.3.2.2	Verify error free transmission of DBPSK type A frames in channel ch 1	PASS	TT
2.3.3.1	Verify error free reception of DBPSK_C type A frames in channel ch 1	PASS	TT
2.3.3.2	Verify error free transmission of DBPSK_C type A frames in channel ch 1	PASS	TT
2.3.4.1	Verify error free reception of DQPSK type A frames in channel ch 1	PASS	TT
2.3.4.2	Verify error free transmission of DQPSK type A frames in channel ch 1	PASS	TT
2.3.5.1	Verify error free reception of DQPSK_C type A frames in channel ch 1	PASS	TT
2.3.5.2	Verify error free transmission of DQPSK_C type A frames in channel ch 1	PASS	TT
2.3.6.1	Verify error free reception of D8PSK type A frames in channel ch 1	PASS	TT
2.3.6.2	Verify error free transmission of D8PSK type A frames in channel ch 1	PASS	TT
2.3.7.1	Verify error free reception of D8PSK_C type A frames in channel ch 1	PASS	TT
2.3.7.2	Verify error free transmission of D8PSK_C type A frames in channel ch 1	PASS	TT

2.3.8.1	Verify error free reception of DBPSK type A frames in channel ch 1 (55°)	PASS	TT
2.3.8.2	Verify error free transmission of DBPSK type A frames in channel ch 1 (55°)	PASS	TT
2.3.9.1	Verify error free reception of D8PSK_C type A frames in channel ch 1 (55°)	PASS	TT
2.3.9.2	Verify error free transmission of D8PSK_C type A frames in channel ch 1 (55°)	PASS	TT
Type B Frame			
2.3.10.1	Verify error free reception of DBPSK type B frames in channel ch 1	PASS	TT
2.3.10.2	Verify error free transmission of DBPSK type B frames in channel ch 1	PASS	TT
2.3.11.1	Verify error free reception of DBPSK_C type B frames in channel ch 1	PASS	TT
2.3.11.2	Verify error free transmission of DBPSK_C type B frames in channel ch 1	PASS	TT
2.3.12.1	Verify error free reception of DQPSK type B frames in channel ch 1	PASS	TT
2.3.12.2	Verify error free transmission of DQPSK type B frames in channel ch 1	PASS	TT
2.3.13.1	Verify error free reception of DQPSK_C type B frames in channel ch 1	PASS	TT
2.3.13.2	Verify error free transmission of DQPSK_C type B frames in channel ch 1	PASS	TT
2.3.14.1	Verify error free reception of D8PSK type B frames in channel ch 1	PASS	TT
2.3.14.2	Verify error free transmission of D8PSK type B frames in channel ch 1	PASS	TT
2.3.15.1	Verify error free reception of D8PSK_C type B frames in channel ch 1	PASS	TT
2.3.15.2	Verify error free transmission of D8PSK_C type B frames in channel ch 1	PASS	TT
2.3.16.1	Verify error free reception of Robust DBPSK type B frames in channel ch 1	PASS	TT
2.3.16.2	Verify error free transmission of Robust DBPSK type B frames in channel ch 1	PASS	TT
2.3.17.1	Verify error free reception of Robust DQPSK type B frames in channel ch 1	PASS	TT
2.3.17.2	Verify error free transmission of Robust DQPSK type B frames in channel ch 1	PASS	TT
2.3.18.1	Verify error free reception of DBPSK type B frames in channel ch 1 (55°)	PASS	TT
2.3.18.2	Verify error free transmission of DBPSK type B frames in channel ch 1 (55°)	PASS	TT
2.3.19.1	Verify error free reception of D8PSK_C type B frames in channel ch 1 (55°)	PASS	TT

2.3.19.2	Verify error free transmission of D8PSK_C type B frames in channel ch 1 (55°)	PASS	TT
Type BC Frame			
2.3.20.1	Verify error free reception of DBPSK type BC frames in channel ch 1	PASS	TT
2.3.20.2	Verify error free transmission of DBPSK type BC frames in channel ch 1	PASS	TT
2.3.21.1	Verify error free reception of DBPSK_C type BC frames in channel ch 1	PASS	TT
2.3.21.2	Verify error free transmission of DBPSK_C type BC frames in channel ch 1	PASS	TT
2.3.22.1	Verify error free reception of DQPSK type BC frames in channel ch 1	PASS	TT
2.3.22.2	Verify error free transmission of DQPSK type BC frames in channel ch 1	PASS	TT
2.3.23.1	Verify error free reception of DQPSK_C type BC frames in channel ch 1	PASS	TT
2.3.23.2	Verify error free transmission of DQPSK_C type BC frames in channel ch 1	PASS	TT
2.3.24.1	Verify error free reception of D8PSK type BC frames in channel ch 1	PASS	TT
2.3.24.2	Verify error free transmission of D8PSK type BC frames in channel ch 1	PASS	TT
2.3.25.1	Verify error free reception of D8PSK_C type BC frames in channel ch 1	PASS	TT
2.3.25.2	Verify error free transmission of D8PSK_C type BC frames in channel ch 1	PASS	TT
2.3.26.1	Verify error free reception of Robust DBPSK type BC frames in channel ch 1	PASS	TT
2.3.26.2	Verify error free transmission of Robust DBPSK type BC frames in channel ch 1	PASS	TT
2.3.27.1	Verify error free reception of Robust DQPSK type BC frames in channel ch 1	PASS	TT
2.3.27.2	Verify error free transmission of Robust DQPSK type BC frames in channel ch 1	PASS	TT
2.3.28.1	Verify error free reception of DBPSK type BC frames in channel ch 1 (55°)	PASS	TT
2.3.28.2	Verify error free transmission of DBPSK type BC frames in channel ch 1 (55°)	PASS	TT
2.3.29.1	Verify error free reception of D8PSK_C type BC frames in channel ch 1 (55°)	PASS	TT
2.3.29.2	Verify error free transmission of D8PSK_C type BC frames in channel ch 1 (55°)	PASS	TT
PHY Test Cases: Regulatory category			
Standards EN 50065-1:2011 EN 50065-2-3:2003 + Ec:2003 + A1:2005 EN 50065-7:2001			

PRIME 1.4 MAC layer			Tools
3.2 MAC Test Cases: Service Node Start-up			
3.2.1	Service node start-up (forcing the reception of beacons).	PASS	NT
3.2.2	Service node start-up (No PNPDU are transmitted when DUT receives BPDUs).	PASS	NT
3.2.3	Service node start-up (PNPDUs generation latency, transmission parameters and transmission rate of PNPDU reduced by factor of received PNPDU).	PASS	NT
3.2.4	Service node start-up (Seeking promotion of DUT after an unsuccessful registration process).	PASS	NT
3.2.5	Service Node start-up (Time condition in the transmission of PNPDU)	PASS	NT
3.2.6	Robust mode of Service Node start-up (PNPDU transmission modulation change).	PASS	NT
3.3 MAC Test Cases: Channel Access			
3.3.1	Channel access- Shared Contention Period. Channel is idle	PASS	NT, VT
3.3.2	Channel access- Shared Contention Period. Channel is occupied.	PASS	NT, VT
3.3.3	Channel access- Contention Free Period.	PASS	NT, VT
3.3.4	Channel access- Contention Free Period.	PASS	NT, LT
3.3.5	Channel access-Adaptation to frame structure change (FRA)	PASS	NT, VT
3.3.6	Channel access-Adaptation to frame length change (FRA)	PASS	NT, LT
3.3.7	Switch's beacon transmission time tolerance with respect to frame's beginning time.	PASS	NT
3.4 MAC Test Cases: Registration			
3.4.1	Registration accepted (Base Node available when DUT powers up).	PASS	NT
3.4.2	Registration accepted (Base Node not available when DUT powers up).	PASS	NT
3.4.3	Registration accepted (DUT connected to a Switch node and the Switch node is connected to the Base Node).	PASS	NT *Attenuators needed
3.4.4	Tracking available Switches	PASS	NT, VT
3.4.5	Unregistering process initiated by a terminal node.	PASS	NT, VT
3.4.6	Unregistering process initiated by the Base node.	PASS	NT
3.5 MAC Test Cases: Promotion			
3.5.1	Promotion process initiated by the base node.	PASS	NT
3.5.2	Promotion process initiated by the service node DUT when receiving PNPDU from another device.	PASS	NT
3.5.3	Switching process: 2 levels of switching (DUT1 as a level 1	PASS	NT

	switch).		
3.5.4	Tracking Switches under one node	PASS	NT
3.5.5	Switching process: 2 levels of switching (DUT as a level 2 switch).	PASS	NT *Attenuators needed
3.5.6	Switching process: Multicast switching	PASS	NT
3.5.7	Switching functions: BPDU transmission	PASS	NT, LT
3.5.8	Switching functions: BPDU modulation change initiated by the Base Node	PASS	NT
3.5.9	Switching functions: BPDU modulation change initiated by the DUT	PASS	NT, VT
3.5.10	Promotion rejected by the base node.	PASS	NT
3.5.11	Demotion process initiated by the base node.	PASS	NT
3.5.12	Double Switching process initiated by the DUT.	PASS	NT, LT
3.5.13	DS-enabling promotion rejection from the base node.	PASS	NT
3.5.14	Full demotion process initiated by the base node.	PASS	LT
3.5.15	Double Switching process initiated by the base node.	PASS	NT
3.5.16	DS-enabling promotion rejection by the DUT.	PASS	NT
3.6 MAC Test Cases: Connection			
3.6.1	Connection establishment initiated by the Base node.	PASS	NT
3.6.2	Connection establishment initiated by the Service node.	PASS	NT, VT
3.6.3	Connection establishment rejected by the Base node.	PASS	NT
3.6.4	Connection closing initiated by the Base node.	PASS	NT
3.6.5	Connection closing initiated by the Service node.	PASS	NT, VT
3.7 MAC Test Cases: ARQ			
3.7.1	Verify correct behaviour of the DUT in a setup where the Base Node does not support ARQ.	PASS	NT, VT
3.7.2	Verify correct behaviour of the DUT in a setup where the Base Node does support ARQ.	PASS	NT
3.7.3	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as RX).	PASS	NT
3.7.4	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as TX).	PASS	NT, VT, LT
3.7.5	Verify that the DUT is able to effectively respond against congestion situation.	PASS	NT, LT
3.7.6	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as RX).	PASS	NT, LT
3.7.7	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as RX).	PASS	LT, VT

3.7.8	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as TX).	PASS	NT, LT
3.7.9	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as TX).	PASS	NT, LT
3.8 MAC Test Cases: Alive			
3.8.1	Keep-Alive process (response from DUT as Terminal).	PASS	NT
3.8.2	Keep-Alive process (response from DUT as Switch).	PASS	NT
3.8.3	Keep-Alive process (timeout and disconnect).	PASS	NT
3.8.4	Keep-Alive process (timeout refresh of DUT as a Terminal)	PASS	NT
3.8.5	Keep-Alive process (timeout refresh of DUT as a Switch).	PASS	NT
3.8.6	Keep-Alive process (changes in Keep Alive timeout).	PASS	NT
3.8.7	Keep-Alive process (three levels hierarchy with the DUT as the first level Switch).	PASS	NT, LT
3.8.8	Keep-Alive process (1.3.6 mechanism).	PASS	NT
3.9 MAC Test Cases: Management			
3.9.1	Forced modulation scheme	PASS	NT, VT
3.9.2	Modulation scheme updated with packet header information	PASS	NT, VT, LT
3.9.3	Modulation scheme updated with ALIVE mechanism: lost ACK	PASS	NT, LT
3.9.4	Modulation scheme updated with ALIVE mechanism: lost response	PASS	NT, LT
3.10 MAC Test Cases: Backwards Compatibility			
3.10.1	Service node start-up (No PNPDU are transmitted when DUT receives CBCN).	N.A.	--
3.10.2	Backwards Compatibility Capability at registration	N.A.	--
3.10.3	PNPDUs discarding	N.A.	--
3.10.4	Demotion process initiated by the base node.	N.A.	--
3.10.5	DUT connected through a 1.3.6 Switch node	N.A.	--
3.10.6	Unregistering process initiated by the DUT when connected through a 1.3.6 Switch.	N.A.	--
3.10.7	DUT as a Switch node for a 1.3.6 Terminal node	N.A.	--
3.10.8	DUT as a level 2 switch with a 1.4 "parent" and 1.3.6 "son"	N.A.	--
3.10.9	DUT as a level 2 switch with a 1.3.6 "parent" and 1.3.6 "son"	N.A.	--
3.10.10	DUT as a level 2 switch with a 1.3.6 "parent" and 1.4 "son"	N.A.	--
3.10.11	BC Keep-Alive process (response from DUT).	N.A.	--
3.10.12	BC Keep-Alive process (timeout and disconnect).	N.A.	--
3.10.13	BC Keep-Alive process (changes in Keep Alive timeout).	N.A.	--
3.11 MAC Test Cases: Time Reference			

3.11.1	Verify correct behavior of the DUT in a setup where the Base Node does support time reference.	PASS	NT, LT
3.11.2	Verify correct behavior of the DUT (as the Switch Node) between the Base Node and Auxiliary Device (as Service Node) do support time reference.	PASS	NT, LT
3.11.3	Check each zero cross detection circuits available in the DUT.	PASS	NT, VT, LT
3.12 MAC Test Cases: Security			
3.12.1	Registration process with security profile 1	N.A.	--
3.12.2	Registration process with security profile 2	N.A.	--
3.12.3	Registration rejection with security profile 1	N.A.	--
3.12.4	Registration rejection with security profile 2	N.A.	--
3.12.5	Nonce usage	N.A.	--
3.12.6	Keys updating with a correct KWK	N.A.	--
3.12.7	Keys updating rejection when a wrong KWK is used	N.A.	--
3.12.8	SWK usage	N.A.	--
3.12.9	SWK modification handling	N.A.	--

CONVERGENCE LAYER 1.4			
4.2 CL Test Cases: Convergence sublayer procedures			
4.2.1	Correct establishment and disconnection of 4-32 link	PASS	NT, VT
4.2.2	Verify the correct implementation of the Segmentation at the DUT side. Force the lenght of the data being transmitted to 16 bytes at the DUT..	PASS	NT, VT
4.2.3	Verify the correct implementation of the Reassembly Mechanism at the DUT side. Force the lenght of the data being transmitted to 16 bytes at the Base Node.	PASS	LT, VT
4.2.4	Verify the correct implementation of the Reassembly Mechanism when incorrect CRC is received at the DUT side. Force the lenght of the data being transmitted to 16 bytes at the Base Node.	PASS	LT, VT
4.3 CL Test Cases: Firmware Upgrade			
4.3.1	Firmware upgrade process (unicast).	PASS	NT, LT, VT
4.3.2	Firmware upgrade process (multicast).	PASS	NT, LT, VT
4.3.3	Firmware upgrade page retransmission	PASS	NT, LT, VT
4.3.4	Firmware upgrade process (unicast). EXCEPTION State. Bit error in the signature of the image	PASS	NT, LT, VT
4.3.5	Firmware upgrade process (unicast). EXCEPTION State. Bit error in the image	PASS	NT, LT, VT

4.4 CL Test Cases: DLMS traffic over 4-32 connection		
4.4.1	CS4-32 is able to pass valid DLMS payload between the meter and the test system.	PASS LT, VT
4.5 CL Test Cases: PRIME Management Plane Communication Profile		
4.5.1	Get PIB attribute query	PASS NT
4.5.2	Set PIB attribute query	PASS NT
4.5.3	Reboot device	PASS NT

For more detailed information about the test results see Annex I

3.- SUMMARY OF TEST RESULTS FOR CHANNEL 5

For each extra Channel these are the test-cases required to apply for Certification according to PRIME Certification 1.4 Service Node Test book v2.9.:

- PHY LAYER: COMPLETE
- MAC LAYER: 3.2.5, 3.3.1, 3.3.3, 3.4.1, 3.5.2, 3.6.2, 3.8.2, 3.9.2
- CONVERGENCE LAYER: 4.2.1, 4.3.1, 4.5.1

For the Convergence Layer TECNALIA has added three more tests to be applied considered critical for the conformance of the device under test: 4.4.1, 4.5.2, 4.5.3.

Tools used for Certification

- Microchip Prime Manager Vendor Tool (VT) to configure the DUT, trigger actions, and confirm manually MAC and CL tests result. Also used as auxiliary SW to run some MAC and CL tests.
- Neuron Conformance Test Tool (NT) to run testcases defined in PRIME Certification 1.4 Service Node Test book v2.9.
- Tecnalia Testing Tool (TT) to run testcases defined in PRIME Certification 1.4 Service Node Test book v2.9.
- Tecnalia Lab. Auxiliary tools (LT) to run MAC and CL tests when needed and to check manually testcases to confirm final result.

PRIME 1.4 PHY Layer			Tools
2.5 PHY Test Cases: Transmission and reception test cases			
Type A Frame			
2.3.2.1	Verify error free reception of DBPSK type A frames in channel ch 5	PASS	TT
2.3.2.2	Verify error free transmission of DBPSK type A frames in channel ch 5	PASS	TT
2.3.3.1	Verify error free reception of DBPSK_C type A frames in channel ch 5	PASS	TT
2.3.3.2	Verify error free transmission of DBPSK_C type A frames in channel ch 5	PASS	TT
2.3.4.1	Verify error free reception of DQPSK type A frames in channel ch 5	PASS	TT
2.3.4.2	Verify error free transmission of DQPSK type A frames in channel ch 5	PASS	TT
2.3.5.1	Verify error free reception of DQPSK_C type A frames in channel ch 5	PASS	TT
2.3.5.2	Verify error free transmission of DQPSK_C type A frames in channel ch 5	PASS	TT

2.3.6.1	Verify error free reception of D8PSK type A frames in channel ch 5	PASS	TT
2.3.6.2	Verify error free transmission of D8PSK type A frames in channel ch 5	PASS	TT
2.3.7.1	Verify error free reception of D8PSK_C type A frames in channel ch 5	PASS	TT
2.3.7.2	Verify error free transmission of D8PSK_C type A frames in channel ch 5	PASS	TT
2.3.8.1	Verify error free reception of DBPSK type A frames in channel ch 5 (55°)	PASS	TT
2.3.8.2	Verify error free transmission of DBPSK type A frames in channel ch 5 (55°)	PASS	TT
2.3.9.1	Verify error free reception of D8PSK_C type A frames in channel ch 5 (55°)	PASS	TT
2.3.9.2	Verify error free transmission of D8PSK_C type A frames in channel ch 5 (55°)	PASS	TT
Type B Frame			
2.3.10.1	Verify error free reception of DBPSK type B frames in channel ch 5	PASS	TT
2.3.10.2	Verify error free transmission of DBPSK type B frames in channel ch 5	PASS	TT
2.3.11.1	Verify error free reception of DBPSK_C type B frames in channel ch 5	PASS	TT
2.3.11.2	Verify error free transmission of DBPSK_C type B frames in channel ch 5	PASS	TT
2.3.12.1	Verify error free reception of DQPSK type B frames in channel ch 5	PASS	TT
2.3.12.2	Verify error free transmission of DQPSK type B frames in channel ch 5	PASS	TT
2.3.13.1	Verify error free reception of DQPSK_C type B frames in channel ch 5	PASS	TT
2.3.13.2	Verify error free transmission of DQPSK_C type B frames in channel ch 5	PASS	TT
2.3.14.1	Verify error free reception of D8PSK type B frames in channel ch 5	PASS	TT
2.3.14.2	Verify error free transmission of D8PSK type B frames in channel ch 5	PASS	TT
2.3.15.1	Verify error free reception of D8PSK_C type B frames in channel ch 5	PASS	TT
2.3.15.2	Verify error free transmission of D8PSK_C type B frames in channel ch 5	PASS	TT
2.3.16.1	Verify error free reception of Robust DBPSK type B frames in channel ch 5	PASS	TT
2.3.16.2	Verify error free transmission of Robust DBPSK type B frames in channel ch 5	PASS	TT
2.3.17.1	Verify error free reception of Robust DQPSK type B frames in channel ch 5	PASS	TT

2.3.17.2	Verify error free transmission of Robust DQPSK type B frames in channel ch 5	PASS	TT
2.3.18.1	Verify error free reception of DBPSK type B frames in channel ch 5 (55°)	PASS	TT
2.3.18.2	Verify error free transmission of DBPSK type B frames in channel ch 5 (55°)	PASS	TT
2.3.19.1	Verify error free reception of D8PSK_C type B frames in channel ch 5 (55°)	PASS	TT
2.3.19.2	Verify error free transmission of D8PSK_C type B frames in channel ch 5 (55°)	PASS	TT
Type BC Frame			
2.3.20.1	Verify error free reception of DBPSK type BC frames in channel ch 5	PASS	TT
2.3.20.2	Verify error free transmission of DBPSK type BC frames in channel ch 5	PASS	TT
2.3.21.1	Verify error free reception of DBPSK_C type BC frames in channel ch 5	PASS	TT
2.3.21.2	Verify error free transmission of DBPSK_C type BC frames in channel ch 5	PASS	TT
2.3.22.1	Verify error free reception of DQPSK type BC frames in channel ch 5	PASS	TT
2.3.22.2	Verify error free transmission of DQPSK type BC frames in channel ch 5	PASS	TT
2.3.23.1	Verify error free reception of DQPSK_C type BC frames in channel ch 5	PASS	TT
2.3.23.2	Verify error free transmission of DQPSK_C type BC frames in channel ch 5	PASS	TT
2.3.24.1	Verify error free reception of D8PSK type BC frames in channel ch 5	PASS	TT
2.3.24.2	Verify error free transmission of D8PSK type BC frames in channel ch 5	PASS	TT
2.3.25.1	Verify error free reception of D8PSK_C type BC frames in channel ch 5	PASS	TT
2.3.25.2	Verify error free transmission of D8PSK_C type BC frames in channel ch 5	PASS	TT
2.3.26.1	Verify error free reception of Robust DBPSK type BC frames in channel ch 5	PASS	TT
2.3.26.2	Verify error free transmission of Robust DBPSK type BC frames in channel ch 5	PASS	TT
2.3.27.1	Verify error free reception of Robust DQPSK type BC frames in channel ch 5	PASS	TT
2.3.27.2	Verify error free transmission of Robust DQPSK type BC frames in channel ch 5	PASS	TT
2.3.28.1	Verify error free reception of DBPSK type BC frames in channel ch 5 (55°)	PASS	TT
2.3.28.2	Verify error free transmission of DBPSK type BC frames in channel ch 5 (55°)	PASS	TT

2.3.29.1	Verify error free reception of D8PSK_C type BC frames in channel ch 5 (55°)	PASS	TT
2.3.29.2	Verify error free transmission of D8PSK_C type BC frames in channel ch 5 (55°)	PASS	TT
PHY Test Cases: Regulatory category			
Not Tested			

PRIME 1.4 MAC layer			Tools
3.2 MAC Test Cases: Service Node Start-up			
3.2.1	Service node start-up (forcing the reception of beacons).	N.A.	--
3.2.2	Service node start-up (No PNPDU are transmitted when DUT receives BPDUs).	N.A.	--
3.2.3	Service node start-up (PNPDUs generation latency, transmission parameters and transmission rate of PNPDU reduced by factor of received PNPDU).	N.A.	--
3.2.4	Service node start-up (Seeking promotion of DUT after an unsuccessful registration process).	N.A.	--
3.2.5	Service Node start-up (Time condition in the transmission of PNPDU)	PASS	NT
3.2.6	Robust mode of Service Node start-up (PNPDU transmission modulation change).	N.A.	--
3.3 MAC Test Cases: Channel Access			
3.3.1	Channel access- Shared Contention Period. Channel is idle	PASS	NT, VT
3.3.2	Channel access- Shared Contention Period. Channel is occupied.	N.A.	--
3.3.3	Channel access- Contention Free Period.	PASS	NT, VT
3.3.4	Channel access- Contention Free Period.	N.A.	--
3.3.5	Channel access-Adaptation to frame structure change (FRA)	N.A.	--
3.3.6	Channel access-Adaptation to frame length change (FRA)	N.A.	--
3.3.7	Switch's beacon transmission time tolerance with respect to frame's beginning time.	N.A.	--
3.4 MAC Test Cases: Registration			
3.4.1	Registration accepted (Base Node available when DUT powers up).	PASS	NT
3.4.2	Registration accepted (Base Node not available when DUT powers up).	N.A.	--
3.4.3	Registration accepted (DUT connected to a Switch node and the Switch node is connected to the Base Node).	N.A.	--
3.4.4	Tracking available Switches	N.A.	--

3.4.5	Unregistering process initiated by a terminal node.	N.A.	--
3.4.6	Unregistering process initiated by the Base node.	N.A.	--
3.5 MAC Test Cases: Promotion			
3.5.1	Promotion process initiated by the base node.	N.A.	--
3.5.2	Promotion process initiated by the service node DUT when receiving PNPDU from another device.	PASS	NT
3.5.3	Switching process: 2 levels of switching (DUT1 as a level 1 switch).	N.A.	--
3.5.4	Tracking Switches under one node	N.A.	--
3.5.5	Switching process: 2 levels of switching (DUT as a level 2 switch).	N.A.	--
3.5.6	Switching process: Multicast switching	N.A.	--
3.5.7	Switching functions: BPDU transmission	N.A.	--
3.5.8	Switching functions: BPDU modulation change initiated by the Base Node	N.A.	--
3.5.9	Switching functions: BPDU modulation change initiated by the DUT	N.A.	--
3.5.10	Promotion rejected by the base node.	N.A.	--
3.5.11	Demotion process initiated by the base node.	N.A.	--
3.5.12	Double Switching process initiated by the DUT.	N.A.	--
3.5.13	DS-enabling promotion rejection from the base node.	N.A.	--
3.5.14	Full demotion process initiated by the base node.	N.A.	--
3.5.15	Double Switching process initiated by the base node.	N.A.	--
3.5.16	DS-enabling promotion rejection by the DUT.	N.A.	--
3.6 MAC Test Cases: Connection			
3.6.1	Connection establishment initiated by the Base node.	N.A.	--
3.6.2	Connection establishment initiated by the Service node.	PASS	NT, VT
3.6.3	Connection establishment rejected by the Base node.	N.A.	--
3.6.4	Connection closing initiated by the Base node.	N.A.	--
3.6.5	Connection closing initiated by the Service node.	N.A.	--
3.7 MAC Test Cases: ARQ			
3.7.1	Verify correct behaviour of the DUT in a setup where the Base Node does not support ARQ.	N.A.	--
3.7.2	Verify correct behaviour of the DUT in a setup where the Base Node does support ARQ.	N.A.	--
3.7.3	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as RX).	N.A.	--
3.7.4	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as TX).	N.A.	--
3.7.5	Verify that the DUT is able to effectively respond against	N.A.	--

	congestion situation.		
3.7.6	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as RX).	N.A.	--
3.7.7	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as RX).	N.A.	--
3.7.8	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as TX).	N.A.	--
3.7.9	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as TX).	N.A.	--
3.8 MAC Test Cases: Alive			
3.8.1	Keep-Alive process (response from DUT as Terminal).	N.A.	--
3.8.2	Keep-Alive process (response from DUT as Switch).	PASS	NT
3.8.3	Keep-Alive process (timeout and disconnect).	N.A.	--
3.8.4	Keep-Alive process (timeout refresh of DUT as a Terminal)	N.A.	--
3.8.5	Keep-Alive process (timeout refresh of DUT as a Switch).	N.A.	--
3.8.6	Keep-Alive process (changes in Keep Alive timeout).	N.A.	--
3.8.7	Keep-Alive process (three levels hierarchy with the DUT as the first level Switch).	N.A.	--
3.8.8	Keep-Alive process (1.3.6 mechanism).	N.A.	--
3.9 MAC Test Cases: Management			
3.9.1	Forced modulation scheme	N.A.	--
3.9.2	Modulation scheme updated with packet header information	PASS	NT, VT, LT
3.9.3	Modulation scheme updated with ALIVE mechanism: lost ACK	N.A.	--
3.9.4	Modulation scheme updated with ALIVE mechanism: lost response	N.A.	--
3.10 MAC Test Cases: Backwards Compatibility			
3.10.1	Service node start-up (No PNPDU are transmitted when DUT receives CBCN).	N.A.	--
3.10.2	Backwards Compatibility Capability at registration	N.A.	--
3.10.3	PNPDUs discarding	N.A.	--
3.10.4	Demotion process initiated by the base node.	N.A.	--
3.10.5	DUT connected through a 1.3.6 Switch node	N.A.	--
3.10.6	Unregistering process initiated by the DUT when connected through a 1.3.6 Switch.	N.A.	--
3.10.7	DUT as a Switch node for a 1.3.6 Terminal node	N.A.	--
3.10.8	DUT as a level 2 switch with a 1.4 "parent" and 1.3.6 "son"	N.A.	--
3.10.9	DUT as a level 2 switch with a 1.3.6 "parent" and 1.3.6 "son"	N.A.	--

3.10.10	DUT as a level 2 switch with a 1.3.6 “parent” and 1.4 “son”	N.A.	--
3.10.11	BC Keep-Alive process (response from DUT).	N.A.	--
3.10.12	BC Keep-Alive process (timeout and disconnect).	N.A.	--
3.10.13	BC Keep-Alive process (changes in Keep Alive timeout).	N.A.	--
3.11 MAC Test Cases: Time Reference			
3.11.1	Verify correct behavior of the DUT in a setup where the Base Node does support time reference.	N.A.	--
3.11.2	Verify correct behavior of the DUT (as the Switch Node) between the Base Node and Auxiliary Device (as Service Node) do support time reference.	N.A.	--
3.11.3	Check each zero cross detection circuits available in the DUT.	N.A.	--
3.12 MAC Test Cases: Security			
3.12.1	Registration process with security profile 1	N.A.	--
3.12.2	Registration process with security profile 2	N.A.	--
3.12.3	Registration rejection with security profile 1	N.A.	--
3.12.4	Registration rejection with security profile 2	N.A.	--
3.12.5	Nonce usage	N.A.	--
3.12.6	Keys updating with a correct KWK	N.A.	--
3.12.7	Keys updating rejection when a wrong KWK is used	N.A.	--
3.12.8	SWK usage	N.A.	--
3.12.9	SWK modification handling	N.A.	--

CONVERGENCE LAYER 1.4			
4.2 CL Test Cases: Convergence sublayer procedures			
4.2.1	Correct establishment and disconnection of 4-32 link	PASS	NT, VT
4.2.2	Verify the correct implementation of the Segmentation at the DUT side. Force the lenght of the data being transmitted to 16 bytes at the DUT..	N.A.	--
4.2.3	Verify the correct implementation of the Reassembly Mechanism at the DUT side. Force the lenght of the data being transmitted to 16 bytes at the Base Node.	N.A.	--
4.2.4	Verify the correct implementation of the Reassembly Mechanism when incorrect CRC is received at the DUT side. Force the lenght of the data being transmitted to 16 bytes at the Base Node.	N.A.	--
4.3 CL Test Cases: Firmware Upgrade			
4.3.1	Firmware upgrade process (unicast).	PASS	NT, VT, LT

4.3.2	Firmware upgrade process (multicast).	N.A.	--
4.3.3	Firmware upgrade page retransmission	N.A.	--
4.3.4	Firmware upgrade process (unicast). EXCEPTION State. Bit error in the signature of the image	N.A.	--
4.3.5	Firmware upgrade process (unicast). EXCEPTION State. Bit error in the image	N.A.	--
4.4 CL Test Cases: DLMS traffic over 4-32 connection			
4.4.1	CS4-32 is able to pass valid DLMS payload between the meter and the test system.	PASS	LT, VT
4.5 CL Test Cases: PRIME Management Plane Communication Profile			
4.5.1	Get PIB attribute query	PASS	NT
4.5.2	Set PIB attribute query	PASS	NT
4.5.3	Reboot device	PASS	NT

For more detailed information about the test results see Annex I

4.- APPLICANT

Miran Černý

ZPA Smart Energy a.s.

Komenského 821, 541 01 Trutnov, CZECH REPUBLIC

5.- PLACE OF RECEPTION AND EXECUTION OF THE TESTS

The reception of the equipment took place in the Smart Data & Protocol Laboratory of TECNALIA, in Derio (Spain).

The performing of the test took place in Smart Data & Protocol Laboratory of TECNALIA, in Derio (Spain).

6.- STANDARDS AND TEST PROCEDURES EMPLOYED

Standards:

- PRIME-Specs V1.4: Specification for Power line Intelligent Metering Evolution. Version 1.4
- EN 50065-1 (2001): "Signalling on low-voltage electrical installations in the frequency range 3 kHz to 148.5 kHz. Part 1: General requirements, frequency bands and electromagnetic disturbances".
- EN 50065-2-3 (2003) + A1 (2005): "Signalling on low-voltage electrical installations in the frequency range 3 kHz to 148.5 kHz. Part 2-3: Immunity requirements for mains communications equipment and systems operating in the range of frequencies of 3 kHz to 95 kHz and intended for use by electricity suppliers and distributors".
- EN 50065-7 (2001): "Signalling on low-voltage electrical installations in the frequency range 3 kHz to 148.5 kHz. Part 7: Equipment impedance".

Testing procedures:

- PRIME Certification 1.4 Service Node Test book v2.9.
- PRIME Certification 1.4 Service Node Test book v2.12. Annex H Basic FCC test suite

7.- CONCLUSIONS

In view of the results and in the test conditions expressed in the present report, the tested sample of:

Unit:	SINGLE-PHASE smart meter with integrated PRIME Power Line Communications
Model:	AM170
Trade Mark:	ZPA Smart Energy a.s.
Serial Number:	M1: nº 18101760 (MAC 11:22:33:00:00:3C) M2: nº 18101761 (MAC 11:22:33:00:00:3D)
Manufacturer:	ZPA Smart Energy a.s.

✓ **COMPLIES** with:

- ✓ Profile: Electricity Meter with PRIME PHY and PRIME MAC. PRIME 1.4 CH1, CH5
 - ✓ PRIME 1.4 PHY
 - ✓ PRIME 1.4 MAC layer
 - Excluding security profiles
 - Excluding backward compatibility.
 - ✓ PRIME 1.4 Convergence layer

In the conditions expressed in sections 2 and 3 of this report.

- This test report is granted on account of tests made at location of TECNALIA, in Derio (Spain).
- The results of the present report apply only to the samples tested and the moment and conditions under which the measurements were performed.
- The complete results, including remarks and limitations, are laid down in ANNEX I of this report.

ANNEX I. TEST RESULTS

Place: Smart Data & Protocol Laboratory in TECNALIA
Electronic devices Laboratory in TECNALIA

Climatic conditions: 19 °C 44% H.R. 1014 mbar

Responsible: Ibone G^a-Borreguero Melero

Used instruments:

Measurement instruments	
X	Tecnaia PRIME 1.4 SN Testing Tool (TT)
X	SD&P Laboratory auxiliary tools (LT)
X	SW Neuron PRIME 1.4 SN Certification Testing Tool (NT) ✓ PRIME v1.4 Conformance Tester (release 2018-09-RC2)
X	HW Neuron PRIME 1.4 SN Certification Testing Tool ✓ BASE NODE ✓ AUX1 ✓ AUX2 ✓ AUX3 ✓ AUX4 ✓ SNIFFER ✓ CONTROL UNIT
X	EL092142 – LISN
X	EL092115 – LISN PRIME
X	EL052008 - CLIMATIC CHAMBER
X	EL022011 - DIGITAL OSCILLOSCOPE
X	EL082055 – ISOLATING TRANSFORM
Data registers storage place	
C.U.	Neuron PRIME 1.4 SN CTT Control Unit
LAB. PC1	C:/Clientes/PRIME14_ELECTROMETER


Used instruments provided by the manufacturer:

Measurement instruments	
X	SW Microchip ✓ Vendor Tool: Microchip PRIME Manager Rev 2.1.0rc3 (VT)


Results:

A.1. PHY layer

A.1.1. Test setup



✓ TECNALIA PRIME 1.4 SN TESTING TOOL (TT)




DUT connections:





Serial Port:



- to manage the DUT
- connected to auxiliary PC to configure the DUT in different modes (PHY tx, PHY rx)
- to access to PIB values
- DUT has to be configured in PHY reception and PHY transmission mode.
- Microchip Prime Manager Vendor Tool and serial terminal emulator Putty:
 - to manage and configure the DUT in PHY mode RX/TX
 - to read PIB attributes







Oscilloscope:

- To measure the frequency band
- To measure the output level of the PRIME signal









A.1.2. PHY Test results for CHANNEL 1

PHY LAYER 1.4						
CODE	DESCRIPTION	RESULT	EXPECTED	STAT.	COMMENTS	TOOL
2.5 PHY Test Cases: Transmission and reception test cases						
Type A Frame						
2.3.2.1	Verify error free reception of DBPSK type A frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.2.2	Verify error free transmission of DBPSK type A frames in channel ch 1	Frames: 1998	at least 1996 frames	PASS	Sample: M1	TT
2.3.3.1	Verify error free reception of DBPSK_C type A frames in channel ch 1	Frames: 1999	at least 1996 frames	PASS	Sample: M1	TT
2.3.3.2	Verify error free transmission of DBPSK_C type A frames in channel ch 1	Frames: 1998	at least 1996 frames	PASS	Sample: M1	TT
2.3.4.1	Verify error free reception of DQPSK type A frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.4.2	Verify error free transmission of DQPSK type A frames in channel ch 1	Frames: 1998	at least 1996 frames	PASS	Sample: M1	TT
2.3.5.1	Verify error free reception of DQPSK_C type A frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT

2.3.5.2	Verify error free transmission of DQPSK_C type A frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.6.1	Verify error free reception of D8PSK type A frames in channel ch 1	Frames: 1999 18,07 dB	at least 1996 frames EVM above 17dB	PASS	Sample: M1	TT
2.3.6.2	Verify error free transmission of D8PSK type A frames in channel ch 1	Frames: 2000 18,15 dB	at least 1996 frames EVM above 17dB	PASS	Sample: M1	TT
2.3.7.1	Verify error free reception of D8PSK_C type A frames in channel ch 1	Frames: 1998	at least 1996 frames	PASS	Sample: M1	TT
2.3.7.2	Verify error free transmission of D8PSK_C type A frames in channel ch 1	Frames: 1999	at least 1996 frames	PASS	Sample: M1	TT
2.3.8.1	Verify error free reception of DBPSK type A frames in channel ch 1 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.8.2	Verify error free transmission of DBPSK type A frames in channel ch 1 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.9.1	Verify error free reception of D8PSK_C type A frames in channel ch 1 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT

2.3.9.2	Verify error free transmission of DBPSK_C type A frames in channel ch 1 (55°)	Frames: 1999	at least 1996 frames	PASS	Sample: M2	TT
Type B Frame						
2.3.10.1	Verify error free reception of DBPSK type B frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.10.2	Verify error free transmission of DBPSK type B frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.11.1	Verify error free reception of DBPSK_C type B frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.11.2	Verify error free transmission of DBPSK_C type B frames in channel ch 1	Frames: 1998	at least 1996 frames	PASS	Sample: M1	TT
2.3.12.1	Verify error free reception of DQPSK type B frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.12.2	Verify error free transmission of DQPSK type B frames in channel ch 1	Frames: 1999	at least 1996 frames	PASS	Sample: M1	TT
2.3.13.1	Verify error free reception of DQPSK_C type B frames in channel ch 1	Frames: 1997	at least 1996 frames	PASS	Sample: M1	TT

2.3.13.2	Verify error free transmission of DQPSK_C type B frames in channel ch 1	Frames: 1999	at least 1996 frames	PASS	Sample: M1	TT
2.3.14.1	Verify error free reception of D8PSK type B frames in channel ch 1	Frames: 2000 18,06 dB	at least 1996 frames EVM above 17dB	PASS	Sample: M1	TT
2.3.14.2	Verify error free transmission of D8PSK type B frames in channel ch 1	Frames: 2000 18,13 dB	at least 1996 frames EVM above 17dB	PASS	Sample: M1	TT
2.3.15.1	Verify error free reception of D8PSK_C type B frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.15.2	Verify error free transmission of D8PSK_C type B frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.16.1	Verify error free reception of Robust DBPSK type B frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.16.2	Verify error free transmission of Robust DBPSK type B frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.17.1	Verify error free reception of Robust DQPSK type B frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT

2.3.17.2	Verify error free transmission of Robust DQPSK type B frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.18.1	Verify error free reception of DBPSK type B frames in channel ch 1 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.18.2	Verify error free transmission of DBPSK type B frames in channel ch 1 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.19.1	Verify error free reception of D8PSK_C type B frames in channel ch 1 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.19.2	Verify error free transmission of D8PSK_C type B frames in channel ch 1 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
Type BC Frame						
2.3.20.1	Verify error free reception of DBPSK type BC frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.20.2	Verify error free transmission of DBPSK type BC frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT

2.3.21.1	Verify error free reception of DBPSK_C type BC frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.21.2	Verify error free transmission of DBPSK_C type BC frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.22.1	Verify error free reception of DQPSK type BC frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.22.2	Verify error free transmission of DQPSK type BC frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.23.1	Verify error free reception of DQPSK_C type BC frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.23.2	Verify error free transmission of DQPSK_C type BC frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.24.1	Verify error free reception of D8PSK type BC frames in channel ch 1	Frames: 2000 18,10 dB	at least 1996 frames EVM above 17dB	PASS	Sample: M1	TT
2.3.24.2	Verify error free transmission of D8PSK type BC frames in channel ch 1	Frames: 2000 18,16 dB	at least 1996 frames EVM above 17dB	PASS	Sample: M1	TT

2.3.25.1	Verify error free reception of D8PSK_C type BC frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.25.2	Verify error free transmission of D8PSK_C type BC frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.26.1	Verify error free reception of Robust DBPSK type BC frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.26.2	Verify error free transmission of Robust DBPSK type BC frames in channel ch 1	Frames: 1999	at least 1996 frames	PASS	Sample: M1	TT
2.3.27.1	Verify error free reception of Robust DQPSK type BC frames in channel ch 1	Frames: 2000	at least 1996 frames	PASS	Sample: M1	TT
2.3.27.2	Verify error free transmission of Robust DQPSK type BC frames in channel ch 1	Frames: 1998	at least 1996 frames	PASS	Sample: M1	TT
2.3.28.1	Verify error free reception of DBPSK type BC frames in channel ch 1 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.28.2	Verify error free transmission of DBPSK type BC frames in channel ch 1 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT

2.3.29.1	Verify error free reception of D8PSK_C type BC frames in channel ch 1 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.29.2	Verify error free transmission of D8PSK_C type BC frames in channel ch 1 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT

A.1.3. PHY Test results for CHANNEL 5

PHY LAYER 1.4						
CODE	DESCRIPTION	RESULT	EXPECTED	STAT.	COMMENTS	TOOL
2.5 PHY Test Cases: Transmission and reception test cases						
Type A Frame						
2.3.2.1	Verify error free reception of DBPSK type A frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.2.2	Verify error free transmission of DBPSK type A frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.3.1	Verify error free reception of DBPSK_C type A frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT

2.3.3.2	Verify error free transmission of DBPSK_C type A frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.4.1	Verify error free reception of DQPSK type A frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.4.2	Verify error free transmission of DQPSK type A frames in channel ch 5	Frames: 1999	at least 1996 frames	PASS	Sample: M2	TT
2.3.5.1	Verify error free reception of DQPSK_C type A frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.5.2	Verify error free transmission of DQPSK_C type A frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.6.1	Verify error free reception of D8PSK type A frames in channel ch 5	Frames: 2000 18,15 dB	at least 1996 frames EVM above 17dB	PASS	Sample: M2	TT
2.3.6.2	Verify error free transmission of D8PSK type A frames in channel ch 5	Frames: 2000 18,15 dB	at least 1996 frames EVM above 17dB	PASS	Sample: M2	TT
2.3.7.1	Verify error free reception of D8PSK_C type A frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT

2.3.7.2	Verify error free transmission of D8PSK_C type A frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.8.1	Verify error free reception of DBPSK type A frames in channel ch 5 (55°)	Frames: 1999	at least 1996 frames	PASS	Sample: M2	TT
2.3.8.2	Verify error free transmission of DBPSK type A frames in channel ch 5 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.9.1	Verify error free reception of D8PSK_C type A frames in channel ch 5 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.9.2	Verify error free transmission of D8PSK_C type A frames in channel ch 5 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
Type B Frame						
2.3.10.1	Verify error free reception of DBPSK type B frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.10.2	Verify error free transmission of DBPSK type B frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT

2.3.11.1	Verify error free reception of DBPSK_C type B frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.11.2	Verify error free transmission of DBPSK_C type B frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.12.1	Verify error free reception of DQPSK type B frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.12.2	Verify error free transmission of DQPSK type B frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.13.1	Verify error free reception of DQPSK_C type B frames in channel ch 5	Frames: 1997	at least 1996 frames	PASS	Sample: M2	TT
2.3.13.2	Verify error free transmission of DQPSK_C type B frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.14.1	Verify error free reception of D8PSK type B frames in channel ch 5	Frames: 2000 18,15 dB	at least 1996 frames EVM above 17dB	PASS	Sample: M2	TT
2.3.14.2	Verify error free transmission of D8PSK type B frames in channel ch 5	Frames: 2000 18,21 dB	at least 1996 frames EVM above 17dB	PASS	Sample: M2	TT

2.3.15.1	Verify error free reception of D8PSK_C type B frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.15.2	Verify error free transmission of D8PSK_C type B frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.16.1	Verify error free reception of Robust DBPSK type B frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.16.2	Verify error free transmission of Robust DBPSK type B frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.17.1	Verify error free reception of Robust DQPSK type B frames in channel ch 5	Frames: 1999	at least 1996 frames	PASS	Sample: M2	TT
2.3.17.2	Verify error free transmission of Robust DQPSK type B frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.18.1	Verify error free reception of DBPSK type B frames in channel ch 5 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.18.2	Verify error free transmission of DBPSK type B frames in channel ch 5 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT

2.3.19.1	Verify error free reception of D8PSK_C type B frames in channel ch 5 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.19.2	Verify error free transmission of D8PSK_C type B frames in channel ch 5 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
Type BC Frame						
2.3.20.1	Verify error free reception of DBPSK type BC frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.20.2	Verify error free transmission of DBPSK type BC frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.21.1	Verify error free reception of DBPSK_C type BC frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.21.2	Verify error free transmission of DBPSK_C type BC frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.22.1	Verify error free reception of DQPSK type BC frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.22.2	Verify error free transmission of DQPSK type BC frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT

2.3.23.1	Verify error free reception of DQPSK_C type BC frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.23.2	Verify error free transmission of DQPSK_C type BC frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.24.1	Verify error free reception of D8PSK type BC frames in channel ch 5	Frames: 2000 18,18 dB	at least 1996 frames EVM above 17dB	PASS	Sample: M2	TT
2.3.24.2	Verify error free transmission of D8PSK type BC frames in channel ch 5	Frames: 2000 18,16 dB	at least 1996 frames EVM above 17dB	PASS	Sample: M2	TT
2.3.25.1	Verify error free reception of D8PSK_C type BC frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.25.2	Verify error free transmission of D8PSK_C type BC frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.26.1	Verify error free reception of Robust DBPSK type BC frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.26.2	Verify error free transmission of Robust DBPSK type BC frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT

2.3.27.1	Verify error free reception of Robust DQPSK type BC frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.27.2	Verify error free transmission of Robust DQPSK type BC frames in channel ch 5	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.28.1	Verify error free reception of DBPSK type BC frames in channel ch 5 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.28.2	Verify error free transmission of DBPSK type BC frames in channel ch 5 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.29.1	Verify error free reception of D8PSK_C type BC frames in channel ch 5 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT
2.3.29.2	Verify error free transmission of D8PSK_C type BC frames in channel ch 5 (55°)	Frames: 2000	at least 1996 frames	PASS	Sample: M2	TT

A.1.4. PHY Test Cases: Regulatory category for CHANNEL 1

DUT is EN50065-1, EN50065-2-3 and EN50065-7 compliant in order to be PRIME compliant.

- According to Test reports No. B41-18-AW-I1 of the Electronic Devices Laboratory of TECNALIA. DUT identification

And the tested sample of:

Unit:	Single-phase smart meter with integrated Prime PLC
Brand:	ZPA SMART ENERGY, A.S.
Model:	AM170
Manufacturer:	ZPA SMART ENERGY, A.S.
PRIME version:	01.03.09.07.0001
Serial number:	n° 0000000018

- **COMPLIES** with EN 50065-1:2011.
- **COMPLIES** with EN 50065-2-3:2003+A1:2005.
- **COMPLIES** with EN 50065-7:2001.

A.2. MAC and CONVERGENCE layer

A.2.1. Test setup

DUT connections:



- Serial port:
 - to configure the DUT in different modes (PHY tx, PHY rx, AppEmu, MAC)
 - to manage the DUT
 - connected to auxiliary PC
 - to access to PIB values with Vendor Tool
 - connected to Neuron Prime 1.4 Certification Testing Tool

Auxiliary PC with the following Software:

- Microchip Vendor Tool PRIME Manager and serial terminal emulator Putty. To configure the DUT in different modes and manage the DUT

DUT configuration for MAC test cases

- Connect serial port to Vendor Tool (VT) or to Putty in auxiliary PC

Testing tools needed for MAC and CL testcases:

- Neuron Prime 1.4 Certification Testing Tool (**NT**)
- Tecnia Lab. auxiliary tools (**LT**) when needed (external sniffers, base nodes and auxiliary Prime 1.4 service nodes, noise generator, oscilloscope)
- Vendor Tool Microchip PRIME Manager Rev 2.1.0rc3 (**VT**)

A.2.2. MAC Test results for CHANNEL 1

PRIME 1.4 MAC layer						
CODE	DESCRIPTION	RESULT	EXPECTED	STAT.	COMMENTS	TOOLS
3.2 MAC Test Cases: Service Node Start-up						
3.2.1	Service node start-up (forcing the reception of beacons).	Successful start-up of Service Node	Successful start-up of Service Node	PASS	Sample: M1	NT
3.2.2	Service node start-up (No PNPDU are transmitted when DUT receives BPDUs).	Successful start-up of Service Node	Successful start-up of Service Node	PASS	Sample: M1	NT
3.2.3	Service node start-up (PNPDUs generation latency, transmission parameters and transmission rate of PNPDU reduced by factor of received PNPDU).	Correct PNPDU generation latency	Correct PNPDU generation latency	PASS	Sample: M1	NT
3.2.4	Service node start-up (Seeking promotion of DUT after an unsuccessful registration process).	Successful promotion of DUT	Successful promotion of DUT	PASS	Sample: M1	NT
3.2.5	Service Node start-up (Time condition in the transmission of PNPDU)	Correct Time condition in TX of PNPDU	Correct randomness in TX of PNPDU	PASS	Sample: M1	NT
3.2.6	Robust mode of Service Node start-up (PNPDU transmission modulation change).	Successful PNPDU modulation change	Successful PNPDU modulation change	PASS	Sample: M1	NT
3.3 MAC Test Cases: Channel Access						

3.3.1	Channel access-Shared Contention Period. Channel is idle	Data sent during SCP	Data sent during SCP	PASS	Sample: M1	NT, VT to Trigger TX_DATA Burst
3.3.2	Channel access-Shared Contention Period. Channel is occupied.	MacCSMAC hBusyCount > MacCSMAF ailCount	MacCSMAC hBusyCount > MacCSMAF ailCount	PASS	Sample: M1	NT, VT to Trigger sn_tx_data
3.3.3	Channel access-Contention Free Period.	DUT does not transmit during CFP	DUT does not transmit during CFP	PASS	Sample: M1	NT, VT to Trigger TX_DATA Burst
3.3.4	Channel access-Contention Free Period.	Successful beacon modulation change	Successful beacon modulation change	PASS	Sample: M1	NT, LT Test-case edited by Tecnalia
3.3.5	Channel access-Adaptation to frame structure change (FRA)	Successful modification of frame structure	Successful modification of frame structure	PASS	Sample: M1	NT, VT to Trigger sn_tx_data
3.3.6	Channel access-Adaptation to frame length change (FRA)	Successful modification of frame length	Successful modification of frame length	PASS	Sample: M1	NT, LT confirm manually
3.3.7	Switch's beacon transmission time tolerance with respect to frame's beginning time.	Correct beacon transmission time tolerance	Correct beacon transmission time tolerance	PASS	Sample: M1	NT
3.4 MAC Test Cases: Registration						
3.4.1	Registration accepted (Base Node available when DUT powers up).	Successful registration to Base Node	Successful registration to Base Node	PASS	Sample: M1	NT
3.4.2	Registration accepted (Base Node not available when DUT powers up).	Successful registration to Base Node	Successful registration to Base Node	PASS	Sample: M1	NT
3.4.3	Registration accepted (DUT connected to a Switch node and the Switch node is connected to the	Successful registration through switch	Successful registration through switch	PASS	Sample: M1	NT *Attenuators needed

Base Node).						
3.4.4	Tracking available Switches	MACListAvailableSwitches contains both available switches	MACListAvailableSwitches contains both available switches	PASS	Sample: M1	NT, VT to Trigger unregistration and to confirm manually
3.4.5	Unregistering process initiated by a terminal node.	Successful unregistration	Successful unregistration	PASS	Sample: M1	NT, VT to trigger unreg
3.4.6	Unregistering process initiated by the Base node.	Successful unregistration	Successful unregistration	PASS	Sample: M1	NT
3.5 MAC Test Cases: Promotion						
3.5.1	Promotion process initiated by the base node.	Successful promotion process	Successful promotion process	PASS	Sample: M1	NT
3.5.2	Promotion process initiated by the service node DUT when receiving PNPDU from another device.	Successful promotion process	Successful promotion process	PASS	Sample: M1	NT
3.5.3	Switching process: 2 levels of switching (DUT1 as a level 1 switch).	Successful switching proces	Successful switching proces	PASS	Sample: M1	NT
3.5.4	Tracking Switches under one node	Successful switching proces	Successful switching proces	PASS	Sample: M1	NT
3.5.5	Switching process: 2 levels of switching (DUT as a level 2 switch).	Successful switching proces	Successful switching proces	PASS	Sample: M1	NT*Attenuators needed
3.5.6	Switching process: Multicast switching	Successful multicast switching proces	Successful multicast switching proces	PASS	Sample: M1	NT
3.5.7	Switching functions: BPDU transmission	Correct BPDU transmission	Correct BPDU transmission	PASS	Sample: M1	NT, LT testcase edited by Tecnalia

3.5.8	Switching functions: BPDU modulation change initiated by the Base Node	Correct BPDU modulation change	Correct BPDU modulation change	PASS	Sample: M1	NT
3.5.9	Switching functions: BPDU modulation change initiated by the DUT	Correct BPDU modulation change	Correct BPDU modulation change	PASS	Sample: M1	NT, VT to trigger mod.change
3.5.10	Promotion rejected by the base node.	Correct behaviour for promotion rejection	Correct behaviour for promotion rejection	PASS	Sample: M1	NT
3.5.11	Demotion process initiated by the base node.	Successful demotion process	Successful demotion process	PASS	Sample: M1	NT
3.5.12	Double Switching process initiated by the DUT.	Successful Double Switching process	Successful Double Switching process	PASS	Sample: M1	NT, LT for external BN, confirm manually, testcase edited by Tecnalia
3.5.13	DS-enabling promotion rejection from the base node.	Successful DS-rejection process	Successful DS-rejection process	PASS	Sample: M1	NT
3.5.14	Full demotion process initiated by the base node.	Successful DS-demotion process	Successful DS-demotion process	PASS	Sample: M1	LT, confirm manually
3.5.15	Double Switching process initiated by the base node.	Successful Double Switching process	Successful Double Switching process	PASS	Sample: M1	NT
3.5.16	DS-enabling promotion rejection by the DUT.	Successful DS-rejection process	Successful DS-rejection process	PASS	Sample: M1	NT
3.6 MAC Test Cases: Connection						
3.6.1	Connection establishment initiated by the Base node.	Successful connection establishment	Successful connection establishment	PASS	Sample: M1	NT

3.6.2	Connection establishment initiated by the Service node.	Successful connection establishment	Successful connection establishment	PASS	Sample: M1	NT, VT to trigger 4_32 conn
3.6.3	Connection establishment rejected by the Base node.	Correct behaviour after rejection of connection	Correct behaviour after rejection of connection	PASS	Sample: M1	NT
3.6.4	Connection closing initiated by the Base node.	Successful connection closing	Successful connection closing	PASS	Sample: M1	NT
3.6.5	Connection closing initiated by the Service node.	Successful connection closing	Successful connection closing	PASS	Sample: M1	NT, VT to trigger conn_close
3.7 MAC Test Cases: ARQ						
3.7.1	Verify correct behaviour of the DUT in a setup where the Base Node does not support ARQ.	CON messages transmitted with CON.ARQ = 0	CON messages transmitted with CON.ARQ = 0	PASS	Sample: M1	NT, VT to establish 4_32 conn
3.7.2	Verify correct behaviour of the DUT in a setup where the Base Node does support ARQ.	CON messages transmitted with CON.ARQ = 1	CON messages transmitted with CON.ARQ = 1	PASS	Sample: M1	NT
3.7.3	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as RX).	ARQ mechanism implemented in the DUT according to clause 4.7.3	ARQ mechanism implemented in the DUT according to clause 4.7.3	PASS	Sample: M1	NT
3.7.4	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as TX).	DUT resends PPDUs that it does not receive ACK for	DUT resends PPDUs that it does not receive ACK for	PASS	Sample: M1	NT, VT to trigger TX DUT, LT to confirm manually, testcase edited by Tecnalia

3.7.5	Verify that the DUT is able to effectively respond against congestion situation.	DUT does not send any data for the next ARQCongCl rTime seconds	DUT does not send any data for the next ARQCongCl rTime seconds	PASS	Sample: M1	NT, LT to confirm manually
3.7.6	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as RX).	DUT ACKs at least one PPDU in the reception window size	DUT ACKs at least one PPDU in the reception window size		Sample: M1	NT, LT to confirm manually
3.7.7	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as RX).	ARQ mechanism implemented in the DUT is according to the clause 4.7.3 [1]	ARQ mechanism implemented in the DUT is according to the clause 4.7.3 [1]		Sample: M1	VT, LT for external BN, confirm manually
3.7.8	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as TX).	DUT sends PPDUs, according to the clause 4.7.3 [1].	DUT sends PPDUs, according to the clause 4.7.3 [1].		Sample: M1	NT, LT to confirm manually, testcase edited by Tecnalia
3.7.9	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as TX).	DUT sends PPDUs, according to the clause 4.7.3 [1].	DUT sends PPDUs, according to the clause 4.7.3 [1].		Sample: M1	NT, LT to confirm manually, testcase edited by Tecnalia
3.8 MAC Test Cases: Alive						

3.8.1	Keep-Alive process (response from DUT as Terminal).	ALV control packets are transacted with its correct priority	ALV control packets are transacted with its correct priority	PASS	Sample: M1	NT
3.8.2	Keep-Alive process (response from DUT as Switch).	ALV control packets are transacted with its correct priority	ALV control packets are transacted with its correct priority	PASS	Sample: M1	NT
3.8.3	Keep-Alive process (timeout and disconnect).	DUT considers itself unregistered and behaves properly	DUT considers itself unregistered and behaves properly	PASS	Sample: M1	NT
3.8.4	Keep-Alive process (timeout refresh of DUT as a Terminal)	After REG.TIME confirm that the DUT considers itself unregistered	After REG.TIME confirm that the DUT considers itself unregistered	PASS	Sample: M1	NT
3.8.5	Keep-Alive process (timeout refresh of DUT as a Switch).	DUT considers itself unregistered and behaves properly	DUT considers itself unregistered and behaves properly	PASS	Sample: M1	NT
3.8.6	Keep-Alive process (changes in Keep Alive timeout).	DUT considers itself unregistered and behaves properly	DUT considers itself unregistered and behaves properly	PASS	Sample: M1	NT
3.8.7	Keep-Alive process (three levels hierarchy with the DUT as the first level Switch).	ALV control packets are transacted with the correct priority	ALV control packets are transacted with the correct priority	PASS	Sample: M1	NT, LT to confirm manually

3.8.8	Keep-Alive process (1.3.6 mechanism).	ALV control packet is conformant to specifications	ALV control packet is conformant to specifications	PASS	Sample: M1	NT
3.9 MAC Test Cases: Management						
3.9.1	Forced modulation scheme	Modulation scheme of the DUT matches the one indicated by the B.N.	Modulation scheme of the DUT matches the one indicated by the B.N.	PASS	Sample: M2	NT, VT to send 4_32 data
3.9.2	Modulation scheme updated with packet header information	Modulation scheme of the first message from the DUT is the most robust one available	Modulation scheme of the first message from the DUT is the most robust one available	PASS	Sample: M1	NT, VT, LT to confirm manually
3.9.3	Modulation scheme updated with ALIVE mechanism: lost ACK	Response is in the most robust mode	Response is in the most robust mode	PASS	Sample: M2	NT, LT to confirm manually
3.9.4	Modulation scheme updated with ALIVE mechanism: lost response	Messages from the DUT are of the same robustness than the request message	Messages from the DUT are at least of the same robustness than the request message	PASS	Sample: M2	NT, LT to confirm manually
3.10 MAC Test Cases: Backwards Compatibility						
3.10.1	Service node start-up (No PNPDU are transmitted when DUT receives CBCN).	N.A.	N.A.	N.A.		N.A.
3.10.2	Backwards Compatibility Capability at registration	N.A.	N.A.	N.A.		N.A.

3.10.3	PNPDUs discarding	N.A.	N.A.	N.A.	N.A.
3.10.4	Demotion process initiated by the base node.	N.A.	N.A.	N.A.	N.A.
3.10.5	DUT connected through a 1.3.6 Switch node	N.A.	N.A.	N.A.	N.A.
3.10.6	Unregistering process initiated by the DUT when connected through a 1.3.6 Switch.	N.A.	N.A.	N.A.	N.A.
3.10.7	DUT as a Switch node for a 1.3.6 Terminal node	N.A.	N.A.	N.A.	N.A.
3.10.8	DUT as a level 2 switch with a 1.4 “parent” and 1.3.6 “son”	N.A.	N.A.	N.A.	N.A.
3.10.9	DUT as a level 2 switch with a 1.3.6 “parent” and 1.3.6 “son”	N.A.	N.A.	N.A.	N.A.
3.10.10	DUT as a level 2 switch with a 1.3.6 “parent” and 1.4 “son”	N.A.	N.A.	N.A.	N.A.
3.10.11	BC Keep-Alive process (response from DUT).	N.A.	N.A.	N.A.	N.A.
3.10.12	BC Keep-Alive process (timeout and disconnect).	N.A.	N.A.	N.A.	N.A.
3.10.13	BC Keep-Alive process (changes in Keep Alive timeout).	N.A.	N.A.	N.A.	N.A.
3.11 MAC Test Cases: Time Reference					

3.11.1	Verify correct behavior of the DUT in a setup where the Base Node does support time reference.	DUT ignores TREF subheader of any of the received packets	DUT is able to ignore TREF subheader of any of the received packets	PASS	Sample: M2	NT, LT to confirm manually
3.11.2	Verify correct behavior of the DUT (as the Switch Node) between the Base Node and Auxiliary Device (as Service Node) do support time reference.	DUT relays one of the packets transmitted to the Service Node with TREF.TIME field set to 0x80000000.	DUT relays at least one of the packets transmitted to the Service Node with TREF.TIME field set to 0x80000000.	PASS	Sample: M2	NT, LT to confirm manually, testcase edited by Tecnalía
3.11.3	Check each zero cross detection circuits available in the DUT.	Time Reference subheader of the response of the DUT and Base Node is less than ± 1.5 milliseconds	Time Reference subheader of the response of the DUT and Base Node is less than ± 1.5 milliseconds	PASS	Sample: M1	NT, VT, LT to confirm manually
3.12 MAC Test Cases: Security						
3.12.1	Registration process with security profile 1	N.A.	N.A.	N.A.		N.A.
3.12.2	Registration process with security profile 2	N.A.	N.A.	N.A.		N.A.
3.12.3	Registration rejection with security profile 1	N.A.	N.A.	N.A.		N.A.
3.12.4	Registration rejection with security profile 2	N.A.	N.A.	N.A.		N.A.
3.12.5	Nonce usage	N.A.	N.A.	N.A.		N.A.
3.12.6	Keys updating with a correct KWK	N.A.	N.A.	N.A.		N.A.

3.12.7	Keys updating rejection when a wrong KWK is used	N.A.	N.A.	N.A.	N.A.
3.12.8	SWK usage	N.A.	N.A.	N.A.	N.A.
3.12.9	SWK modification handling	N.A.	N.A.	N.A.	N.A.

A.2.3. MAC Test results for CHANNEL 5

PRIME 1.4 MAC layer						
CODE	DESCRIPTION	RESULT	EXPECTED	STAT.	COMMENTS	TOOLS
3.2 MAC Test Cases: Service Node Start-up						
3.2.1	Service node start-up (forcing the reception of beacons).	N.A.	N.A.	N.A.	N.A.	N.A.
3.2.2	Service node start-up (No PNPDU are transmitted when DUT receives BPDUs).	N.A.	N.A.	N.A.	N.A.	N.A.
3.2.3	Service node start-up (PNPDUs generation latency, transmission parameters and transmission rate of PNPDU reduced by factor of received PNPDU).	N.A.	N.A.	N.A.	N.A.	N.A.
3.2.4	Service node start-up (Seeking promotion of DUT after an unsuccessful registration)	N.A.	N.A.	N.A.	N.A.	N.A.

	process).					
3.2.5	Service Node start-up (Time condition in the transmission of PNPDU)	Correct Time condition in TX of PNPDU	Correct randomness in TX of PNPDU	PASS	Sample: M2	NT
3.2.6	Robust mode of Service Node start-up (PNPDU transmission modulation change).	N.A.	N.A.	N.A.	N.A.	N.A.
3.3 MAC Test Cases: Channel Access						
3.3.1	Channel access-Shared Contention Period. Channel is idle	Data sent during SCP	Data sent during SCP	PASS	Sample: M2	NT, VT to Trigger TX_DATA Burst
3.3.2	Channel access-Shared Contention Period. Channel is occupied.	N.A.	N.A.	N.A.	N.A.	N.A.
3.3.3	Channel access-Contention Free Period.	DUT does not transmit during CFP	DUT does not transmit during CFP	PASS	Sample: M2	NT, VT to Trigger TX_DATA Burst
3.3.4	Channel access-Contention Free Period.	N.A.	N.A.	N.A.	N.A.	N.A.
3.3.5	Channel access-Adaptation to frame structure change (FRA)	N.A.	N.A.	N.A.	N.A.	N.A.
3.3.6	Channel access-Adaptation to frame length change (FRA)	N.A.	N.A.	N.A.	N.A.	N.A.
3.3.7	Switch's beacon transmission time tolerance with respect to frame's beginning time.	N.A.	N.A.	N.A.	N.A.	N.A.
3.4 MAC Test Cases: Registration						

3.4.1	Registration accepted (Base Node available when DUT powers up).	Successful registration to Base Node	Successful registration to Base Node	PASS	Sample: M2	NT
3.4.2	Registration accepted (Base Node not available when DUT powers up).	N.A.	N.A.	N.A.	N.A.	N.A.
3.4.3	Registration accepted (DUT connected to a Switch node and the Switch node is connected to the Base Node).	N.A.	N.A.	N.A.	N.A.	N.A.
3.4.4	Tracking available Switches	N.A.	N.A.	N.A.	N.A.	N.A.
3.4.5	Unregistering process initiated by a terminal node.	N.A.	N.A.	N.A.	N.A.	N.A.
3.4.6	Unregistering process initiated by the Base node.	N.A.	N.A.	N.A.	N.A.	N.A.
3.5 MAC Test Cases: Promotion						
3.5.1	Promotion process initiated by the base node.	N.A.	N.A.	N.A.	N.A.	N.A.
3.5.2	Promotion process initiated by the service node DUT when receiving PNPDU from another device.	Successful promotion process	Successful promotion process	PASS	Sample: M2	NT
3.5.3	Switching process: 2 levels of switching (DUT1 as a level 1 switch).	N.A.	N.A.	N.A.	N.A.	N.A.
3.5.4	Tracking Switches under one node	N.A.	N.A.	N.A.	N.A.	N.A.
3.5.5	Switching process: 2 levels of switching (DUT as a level 2 switch).	N.A.	N.A.	N.A.	N.A.	N.A.

3.5.6	Switching process: Multicast switching	N.A.	N.A.	N.A.	N.A.	N.A.
3.5.7	Switching functions: BPDU transmission	N.A.	N.A.	N.A.	N.A.	N.A.
3.5.8	Switching functions: BPDU modulation change initiated by the Base Node	N.A.	N.A.	N.A.	N.A.	N.A.
3.5.9	Switching functions: BPDU modulation change initiated by the DUT	N.A.	N.A.	N.A.	N.A.	N.A.
3.5.10	Promotion rejected by the base node.	N.A.	N.A.	N.A.	N.A.	N.A.
3.5.11	Demotion process initiated by the base node.	N.A.	N.A.	N.A.	N.A.	N.A.
3.5.12	Double Switching process initiated by the DUT.	N.A.	N.A.	N.A.	N.A.	N.A.
3.5.13	DS-enabling promotion rejection from the base node.	N.A.	N.A.	N.A.	N.A.	N.A.
3.5.14	Full demotion process initiated by the base node.	N.A.	N.A.	N.A.	N.A.	N.A.
3.5.15	Double Switching process initiated by the base node.	N.A.	N.A.	N.A.	N.A.	N.A.
3.5.16	DS-enabling promotion rejection by the DUT.	N.A.	N.A.	N.A.	N.A.	N.A.
3.6 MAC Test Cases: Connection						

3.6.1	Connection establishment initiated by the Base node.	N.A.	N.A.	N.A.	N.A.	N.A.
3.6.2	Connection establishment initiated by the Service node.	Successful connection establishment	Successful connection establishment	PASS	Sample: M2	NT, VT to trigger 4_32 conn
3.6.3	Connection establishment rejected by the Base node.	N.A.	N.A.	N.A.	N.A.	N.A.
3.6.4	Connection closing initiated by the Base node.	N.A.	N.A.	N.A.	N.A.	N.A.
3.6.5	Connection closing initiated by the Service node.	N.A.	N.A.	N.A.	N.A.	N.A.
3.7 MAC Test Cases: ARQ						
3.7.1	Verify correct behaviour of the DUT in a setup where the Base Node does not support ARQ.	N.A.	N.A.	N.A.	N.A.	N.A.
3.7.2	Verify correct behaviour of the DUT in a setup where the Base Node does support ARQ.	N.A.	N.A.	N.A.	N.A.	N.A.
3.7.3	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as RX).	N.A.	N.A.	N.A.	N.A.	N.A.

3.7.4	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as TX).	N.A.	N.A.	N.A.	N.A.	N.A.
3.7.5	Verify that the DUT is able to effectively respond against congestion situation.	N.A.	N.A.	N.A.	N.A.	N.A.
3.7.6	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as RX).	N.A.	N.A.	N.A.	N.A.	N.A.
3.7.7	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as RX).	N.A.	N.A.	N.A.	N.A.	N.A.
3.7.8	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as TX).	N.A.	N.A.	N.A.	N.A.	N.A.
3.7.9	Verify correct behaviour of the DUT during a transmission of PPDUs in a setup where the Base Node does support ARQ (DUT as TX).	N.A.	N.A.	N.A.	N.A.	N.A.

3.8 MAC Test Cases: Alive						
3.8.1	Keep-Alive process (response from DUT as Terminal).	N.A.	N.A.	N.A.	N.A.	N.A.
3.8.2	Keep-Alive process (response from DUT as Switch).	ALV control packets are transacted with its correct priority	ALV control packets are transacted with its correct priority	PASS	Sample: M2	NT
3.8.3	Keep-Alive process (timeout and disconnect).	N.A.	N.A.	N.A.	N.A.	N.A.
3.8.4	Keep-Alive process (timeout refresh of DUT as a Terminal)	N.A.	N.A.	N.A.	N.A.	N.A.
3.8.5	Keep-Alive process (timeout refresh of DUT as a Switch).	N.A.	N.A.	N.A.	N.A.	N.A.
3.8.6	Keep-Alive process (changes in Keep Alive timeout).	N.A.	N.A.	N.A.	N.A.	N.A.
3.8.7	Keep-Alive process (three levels hierarchy with the DUT as the first level Switch).	N.A.	N.A.	N.A.	N.A.	N.A.
3.8.8	Keep-Alive process (1.3.6 mechanism).	N.A.	N.A.	N.A.	N.A.	N.A.
3.9 MAC Test Cases: Management						
3.9.1	Forced modulation scheme	N.A.	N.A.	N.A.	N.A.	N.A.
3.9.2	Modulation scheme updated with packet header information	Modulation scheme of the first message from the DUT is the most robust one available	Modulation scheme of the first message from the DUT is the most robust one available	PASS	Sample: M1	NT, VT, LT to confirm manually

3.9.3	Modulation scheme updated with ALIVE mechanism: lost ACK	N.A.	N.A.	N.A.	N.A.	N.A.
3.9.4	Modulation scheme updated with ALIVE mechanism: lost response	N.A.	N.A.	N.A.	N.A.	N.A.
3.10 MAC Test Cases: Backwards Compatibility						
3.10.1	Service node start-up (No PNPDU are transmitted when DUT receives CBCN).	N.A.	N.A.	N.A.		N.A.
3.10.2	Backwards Compatibility Capability at registration	N.A.	N.A.	N.A.		N.A.
3.10.3	PNPDUs discarding	N.A.	N.A.	N.A.		N.A.
3.10.4	Demotion process initiated by the base node.	N.A.	N.A.	N.A.		N.A.
3.10.5	DUT connected through a 1.3.6 Switch node	N.A.	N.A.	N.A.		N.A.
3.10.6	Unregistering process initiated by the DUT when connected through a 1.3.6 Switch.	N.A.	N.A.	N.A.		N.A.
3.10.7	DUT as a Switch node for a 1.3.6 Terminal node	N.A.	N.A.	N.A.		N.A.
3.10.8	DUT as a level 2 switch with a 1.4 "parent" and 1.3.6 "son"	N.A.	N.A.	N.A.		N.A.
3.10.9	DUT as a level 2 switch with a 1.3.6 "parent" and 1.3.6 "son"	N.A.	N.A.	N.A.		N.A.

3.10.10	DUT as a level 2 switch with a 1.3.6 “parent” and 1.4 “son”	N.A.	N.A.	N.A.	N.A.	N.A.
3.10.11	BC Keep-Alive process (response from DUT).	N.A.	N.A.	N.A.	N.A.	N.A.
3.10.12	BC Keep-Alive process (timeout and disconnect).	N.A.	N.A.	N.A.	N.A.	N.A.
3.10.13	BC Keep-Alive process (changes in Keep Alive timeout).	N.A.	N.A.	N.A.	N.A.	N.A.
3.11 MAC Test Cases: Time Reference						
3.11.1	Verify correct behavior of the DUT in a setup where the Base Node does support time reference.	N.A.	N.A.	N.A.	N.A.	N.A.
3.11.2	Verify correct behavior of the DUT (as the Switch Node) between the Base Node and Auxiliary Device (as Service Node) do support time reference.	N.A.	N.A.	N.A.	N.A.	N.A.
3.11.3	Check each zero cross detection circuits available in the DUT.	N.A.	N.A.	N.A.	N.A.	N.A.
3.12 MAC Test Cases: Security						
3.12.1	Registration process with security profile 1	N.A.	N.A.	N.A.	N.A.	N.A.
3.12.2	Registration process with security profile 2	N.A.	N.A.	N.A.	N.A.	N.A.
3.12.3	Registration rejection with security profile 1	N.A.	N.A.	N.A.	N.A.	N.A.

3.12.4	Registration rejection with security profile 2	N.A.	N.A.	N.A.	N.A.
3.12.5	Nonce usage	N.A.	N.A.	N.A.	N.A.
3.12.6	Keys updating with a correct KWK	N.A.	N.A.	N.A.	N.A.
3.12.7	Keys updating rejection when a wrong KWK is used	N.A.	N.A.	N.A.	N.A.
3.12.8	SWK usage	N.A.	N.A.	N.A.	N.A.
3.12.9	SWK modification handling	N.A.	N.A.	N.A.	N.A.

A.2.5. CL Test results for CHANEL 1

CONVERGENCE LAYER 1.4						
CODE	DESCRIPTION	RESULT	EXPECTED	STAT	COMMENTS	TOOLS
4.2 CL Test Cases: Convergence sublayer procedures						
4.2.1	Correct establishment and disconnection of 4-32 link	Successful 4-32 communication	Successful 4-32 communication	PASS	Sample: M2	NT, VT to trigger 4_32 conn
4.2.2	Verify the correct implementation of the Segmentation at the DUT side. Force the length of the data being transmitted to 16 bytes at the DUT.	Successful segmentation process	Successful segmentation process	PASS	Sample: M2	NT, VT to trigger 4_32 conn
4.2.3	Verify the correct implementation of the Reassembly Mechanism at the DUT side. Force the length of the data being transmitted to 16 bytes at the Base Node.	Successful reassembly process	Successful reassembly process	PASS	Sample: M2	VT< to TX data and confirm manually
4.2.4	Verify the correct implementation of the Reassembly Mechanism when incorrect CRC is received at the DUT side. Force the length of the data being transmitted to 16 bytes at the Base Node.	Correct implementation of reassembly process with incorrect CRC	Correct implementation of reassembly process with incorrect CRC	PASS	Sample: M2	VT< for external BN and confirm manually
4.3 CL Test Cases: Firmware Upgrade						
4.3.1	Firmware upgrade process (unicast).	Successful unicast FW Upgrade	Successful unicast FW Upgrade	PASS	Sample: M2	NT, LT to force ideal setup, VT to check manually

4.3.2	Firmware upgrade process (multicast).	Successful multicast FW Upgrade	Successful multicast FW Upgrade	PASS	Sample: M2	NT, LT&VT to check manually
4.3.3	Firmware upgrade page retransmission	Successful FW upgrade with page retransmission	Successful FW upgrade with page retransmission	PASS	Sample: M2	NT, LT&VT to check manually
4.3.4	Firmware upgrade process (unicast). EXCEPTION State. Bit error in the signature of the image	Successful handling of bit error in image signature	Successful handling of bit error in image signature	PASS	Sample: M2	NT, LT&VT to check manually
4.3.5	Firmware upgrade process (unicast). EXCEPTION State. Bit error in the image	Successful handling of bit error in image	Successful handling of bit error in image	PASS	Sample: M2	NT, LT&VT to check manually
4.4 CL Test Cases: DLMS traffic over 4-32 connection						
4.4.1	CS4-32 is able to pass valid DLMS payload between the meter and the test system.	DLMS parameter is correctly obtained	DLMS parameter is correctly obtained	PASS	Sample: M1	LT, VT
4.5 CL Test Cases: PRIME Management Plane Communication Profile						
4.5.1	Get PIB attribute query	Successful reading of PIB attribute	Successful reading of PIB attribute	PASS	Sample: M2	NT
4.5.2	Set PIB attribute query	Successful setting of PIB attribute	Successful setting of PIB attribute	PASS	Sample: M2	NT
4.5.3	Reboot device	Successful rebooting of device	Successful rebooting of device	PASS	Sample: M2	NT

A.2.6. CL Test results for CHANEL 5

CONVERGENCE LAYER 1.4						
CODE	DESCRIPTION	RESULT	EXPECTED	STAT	COMMENTS	TOOLS
4.2 CL Test Cases: Convergence sublayer procedures						
4.2.1	Correct establishment and disconnection of 4-32 link	Successful 4-32 communication	Successful 4-32 communication	PASS	Sample: M2	NT, VT to trigger 4_32 conn
4.2.2	Verify the correct implementation of the Segmentation at the DUT side. Force the length of the data being transmitted to 16 bytes at the DUT.	N.A.	N.A.	N.A.	N.A.	N.A.
4.2.3	Verify the correct implementation of the Reassembly Mechanism at the DUT side. Force the length of the data being transmitted to 16 bytes at the Base Node.	N.A.	N.A.	N.A.	N.A.	N.A.
4.2.4	Verify the correct implementation of the Reassembly Mechanism when incorrect CRC is received at the DUT side. Force the length of the data being transmitted to 16 bytes at the Base Node.	N.A.	N.A.	N.A.	N.A.	N.A.
4.3 CL Test Cases: Firmware Upgrade						
4.3.1	Firmware upgrade process (unicast).	Successful unicast FW Upgrade	Successful unicast FW Upgrade	PASS	Sample: M2	NT, LT to force ideal setup, VT to check manually

4.3.2	Firmware upgrade process (multicast).	N.A.	N.A.	N.A.	N.A.	N.A.
4.3.3	Firmware upgrade page retransmission	N.A.	N.A.	N.A.	N.A.	N.A.
4.3.4	Firmware upgrade process (unicast). EXCEPTION State. Bit error in the signature of the image	N.A.	N.A.	N.A.	N.A.	N.A.
4.3.5	Firmware upgrade process (unicast). EXCEPTION State. Bit error in the image	N.A.	N.A.	N.A.	N.A.	N.A.
4.4 CL Test Cases: DLMS traffic over 4-32 connection						
4.4.1	CS4-32 is able to pass valid DLMS payload between the meter and the test system.	DLMS parameter is correctly obtained	DLMS parameter is correctly obtained	PASS	Sample: M1	LT, VT
4.5 CL Test Cases: PRIME Management Plane Communication Profile						
4.5.1	Get PIB attribute query	Successful reading of PIB attribute	Successful reading of PIB attribute	PASS	Sample: M2	NT
4.5.2	Set PIB attribute query	Successful setting of PIB attribute	Successful setting of PIB attribute	PASS	Sample: M2	NT
4.5.3	Reboot device	Successful rebooting of device	Successful rebooting of device	PASS	Sample: M2	NT

ANNEX II. MODIFICATIONS FROM PRIME 1.3.6 CERTIFIED MODEL AM170 TO CURRENT PRIME 1.4 MODEL MANUFACTURER/DEVELOPER DECLARATION



TECNALIA
Electronic Devices Lab
Smart Data & Protocols Lab
Área DIGITAL SERVICES
Parque Tecnológico de Bizkaia., Edif. 700
48160 Derio (Bizkaia) SPAIN

Trutnov, March 07, 2019


Declaration on AMx70 Electricity Meter Hardware

WHEREAS we, ZPA Smart Energy a.s., member of the El Sewedy group, are a reputable manufacturer having factories at Komenskeho 821, 541 01 Trutnov - Czech Republic, and also bear full responsibility for the development of the Single-phase bidirectional static electricity meter **AM170** and the Three-phase bidirectional static electricity meter **AM370**,

THEREFORE, we do hereby solemnly declare the following:

All the results obtained during the tests carried out on **AM170 PRIME 1.3.6** and **AM370 PRIME 1.3.6** meters as per norm **CENELEC EN50065**, are still valid for **AM170 PRIME 1.4** and **AM370 PRIME 1.4** meters, since they are based on the same HW and only the additional part for PRIME 1.4 is active in the latter.

 **ZPA Smart Energy**
a.s.
Komenského 821, 541 01 Trutnov
IČ: 27445976 DIČ: CZ27445976
tel. +420 499 907 111


Aleš Mikula, MBA

ZPA Smart Energy CTO
Member of the Board