



# Test Report

## No E-22-I-047-JG

PRIME Certification Tests Cases for Service Nodes

<b>EQUIPMENT UNDER TEST</b>	<b>Single phase service node (Electricity meter)</b>
<b>MODEL</b>	<b>MA109H</b>
<b>PRIME FIRMWARE VERSION / COMMUNICATION MODULE FW VERSION</b>	<b>00-4158c20026253 / V5002</b>
<b>CERTIFICATION SCOPE</b>	<b>Profile 3 – Electricity Meter with PRIME chipset</b>

Author: Javier Gómez  
Reviewer: Fernando Lobo

NOTE: This test report shows the detailed information associated with the Test Report Summary no. No E-22-I-046-JG

© DNV GL Services Spain SL, Madrid, Spain. All rights reserved.

This document contains confidential information that shall not be transmitted to any third party without written consent of DNV GL Services Spain SL. The same applies to file copying (including but not limited to electronic copies), wholly or partially.

It is prohibited to change any and all versions of this document in any manner whatsoever, including but not limited to dividing it into parts. In case of a conflict between an electronic version (e.g. PDF file) and the original paper version provided DNV GL Services Spain SL, the latter will prevail.

DNV GL Services Spain SL and/or its associated companies disclaim liability for any direct, indirect, consequential or incidental damages that may result from the use of the information or data, or from the inability to use the information or data contained in this document.

## INDEX

1.-	SUMMARY OF TEST RESULTS .....	4
2.-	APPLICANT .....	6
3.-	PLACE OF RECEPTION AND EXECUTION OF THE TESTS.....	6
4.-	STANDARDS AND TEST PROCEDURES EMPLOYED .....	6
5.-	CONCLUSIONS .....	7
	ANNEX I. TEST RESULTS .....	8

EQUIPMENT UNDER TEST IDENTIFICATION

<b>Unit:</b>	Single phase service node (Electricity meter)
<b>Model:</b>	MA109H
<b>Trademark:</b>	Kaifa
<b>Serial Number:</b>	2200350004
<b>Manufacturer:</b>	Shenzhen Kaifa Technology (Chengdu) Co., Ltd.



The samples were selected and delivered by the applicant.

Equipment characteristics declared by the applicant:

<b>Device type</b>	Single phase service node (Electricity meter)
<b>BaudRate</b>	9600 bps
<b>MAC</b>	10:E7:7A:AF:1C:63
<b>PRIME Firmware version / Communication module FW version</b>	00-4158c20026253 / V5002
<b>Applicable Optional tests</b>	3.4.23
<b>Recertification</b>	NA

## 1.- SUMMARY OF TEST RESULTS

In this chapter gives an overview of the inspection test results for each group of test cases. For detailed review regarding what is tested and all observations (i.e.: comments and remarks that apply to each test case and general exceptions and notes) please check Appendix A.

Major defects are a certain cause for operational risks: these **MUST** be corrected before going into an operational situation! They imply the test is **Fail**.

A remark introduces additional observations about the test case results, like limitations or minor deviations in the implementation. It implies that the test is **Pass with Remark**.

And finally, a comment refers to the additional observations about the test case results that are not directly addressed by the objectives of the subjected test case, so the test is **Pass**.

PHY LAYER		
<b>2.2 PHY Test Cases: Functional Category</b>		
2.2.1	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec and output level 120 dBuV, PPDU length 256 bytes. D8PSK	PASS
2.2.2	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec and output level 120 dBuV,PPDU length 256 bytes. D8PSK+CC	PASS
2.2.3	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec and output level 120 dBuV, PPDU length 256 bytes. DBPSK	PASS
2.2.4	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec and output level 120dBuV, PPDU length 256 bytes. DBPSK+CC	PASS
2.2.5	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec and output level 120 dBuV, PPDU length 256 bytes. Modulation type: DQPSK	PASS
2.2.6	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec and output level 120 dBuV, PPDU length 256 bytes. QPSK+CC	PASS
2.2.7	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec (20hm) and output level 120 dBuV, PPDU length 256 bytes.DBPSK	PASS
2.2.8	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec (20hm) and output level 120 dBuV, PPDU length 256 bytes. D8PSK+CC	PASS
2.2.9	Verify error free communication (0.2% FER) (checking the complete frame payload) when receiving input signal of 122 dBuV. (DUT is in reception state). Modulation type: D8PSK	PASS
<b>2.4 PHY Test Cases: Signal Quality category</b>		
2.4.1	Verify that the EVM of the received signal at output level is above 17dB.	PASS
2.4.2	Verify that the EVM of the transmitted signal output level is above 17dB.	PASS
<b>2.5 PHY Test Cases: Regulatory category</b>		
2.5.1	PHY Test Cases: Regulatory category	PASS
<b>MAC LAYER</b>		
<b>3.2 MAC Test Cases: Service Node Start-up</b>		
3.2.1	Service node start-up (forcing the reception of beacons).	PASS

3.2.2	Service node start-up (No PNPDU are transmit when DUT receives BPDUs).	PASS
3.2.3	Service node start-up (Tx rate of PNPDU reduced by factor of received PNPDU).	PASS
3.2.4	Service node start-up (PNPDU generation latency and transmission parameters).	PASS
3.2.5	Service Node start-up (RANDOMness in the transmission of PNPDU)	PASS
3.2.6	Service Node start-up (seeking promotion of DUT).	PASS
<b>3.3 MAC Test Cases: Channel Access</b>		
3.3.1	Channel access- Shared Contention Period. Channel is idle	PASS
3.3.2	Channel access- Shared Contention Period. Channel is occupied.	PASS
3.3.3	Channel access- Contention Free Period.	PASS
3.3.4	Channel access- Adaptation to frame structure change (FRA)	PASS
<b>3.4 MAC Test Cases: Service Node MAC specific procedures</b>		
3.4.1	Registration accepted (Base Node available when DUT powers up).	PASS
3.4.2	Registration accepted (Base Node not available when DUT powers up).	PASS
3.4.3	Registration accepted (DUT connected to a Switch node and the Switch node is connected to the Base Node).	PASS
3.4.4	Unregistering process initiated by a terminal node.	PASS
3.4.5	Unregistering process initiated by the Base node.	PASS
3.4.6	Promotion process initiated by the base node.	PASS
3.4.7	Promotion process initiated by the service node DUT.	PASS
3.4.8	Switching process: 2 levels of switching (DUT1 as a level 1 switch).	PASS
3.4.9	Switching process: 2 levels of switching (DUT as a level 2 switch).	PASS
3.4.10	Switching functions: BPDU transmission	PASS
3.4.11	Switching functions: BPDU updates from FRA control packet	PASS
3.4.12	Promotion rejected by the base node.	PASS
3.4.13	Demotion process initiated by the base node.	PASS
3.4.14	Keep-Alive process (response from DUT).	PASS
3.4.15	Keep-Alive process (timeout and disconnect).	PASS
3.4.16	Keep-Alive process (changes in Keep Alive timeout).	PASS
3.4.17	Connection establishment initiated by the Base node.	PASS
3.4.18	Connection establishment initiated by the Service node.	PASS
3.4.19	Connection establishment rejected by the Base node.	PASS
3.4.20	Connection closing initiated by the Base node.	PASS
3.4.21	Connection closing initiated by the Service node.	PASS
3.4.22	File transfer process (unicast).	PASS
3.4.23	File transfer process (multicast).	PASS
3.4.24	Error in the firmware upgrade process.	PASS
<b>CONVERGENCE LAYER</b>		
<b>4.2 CL Test Cases: 4-32 Connection establishment</b>		
4.2.1	Correct establishment and disconnection of 4-32 link	PASS
<b>4.3 CL Test Cases: DLMS traffic over 4-32 connection</b>		
4.3.1	CS4-32 is able to pass valid DLMS payload between the meter and the test system.	PASS

For more detailed information about the test results see Annex I

## 2.- APPLICANT

Name: Li Ping Qin

Company Name: Shenzhen Kaifa Technology (Chengdu) Co., Ltd.

Address: No. 99 Tianquan Rd., Hi-Tech Development Zone (West), Chengdu, P.R.C. (PC: 611730)

## 3.- PLACE OF RECEPTION AND EXECUTION OF THE TESTS

Laboratory: DNV

Address: C/ Santa María Magdalena 14, Planta 3, 28016 Madrid, Spain

## 4.- STANDARDS AND TEST PROCEDURES EMPLOYED

Standards:

- Draft Specification for PowerLine Intelligent Metering Evolution. PRIME-Specification v.1.3.6.
- UNE EN 50065-1:2012: Signalling on low-voltage electrical installations in the frequency range 3 kHz to 148.5 kHz - Part 1: General requirements, frequency bands and electromagnetic disturbances.
- UNE EN 50065-2-3:2004 + A1:2006: Signalling on low-voltage electrical installations in the frequency range 3 kHz to 148.5 kHz - Part 2-3: Immunity requirements for mains communications equipment and systems operating in the range of frequencies of 3 kHz to 95 kHz and intended for use by electricity suppliers and distributors.
- UNE EN 50065-7:2002: Signalling on low-voltage electrical installations in the frequency range 3 kHz to 148.5 kHz - Part 7: Equipment impedance.

Testing procedures:

- PRIME Certification. Test Cases version R1.3

## 5.- CONCLUSIONS

In view of the results and in the test conditions expressed in the present report, the tested sample of:

<b>Unit:</b>	Single phase service node
<b>Model:</b>	MA109H
<b>Trade Mark:</b>	Kaifa
<b>Serial Number:</b>	2200350004
<b>Manufacturer:</b>	Shenzhen Kaifa Technology (Chengdu) Co., Ltd.

✓ **COMPLIES** with the tests cases defined by PRIME Alliance in its PRIME Certification. Test Cases version R1.3 based on PRIME-Specification v.1.3.6.

- This test report is granted on account of tests made at location of DNV in Madrid, Spain.
- The results of the present report apply only to the samples tested and the moment and conditions under which the measurements were performed.
- The complete results, including remarks and limitations, are laid down in ANNEX I of this report.

## ANNEX I. TEST RESULTS

**Place:**

DNV Smart Grid Lab

C/ Santa María Magdalena 14, Planta 3, 28016 Madrid, Spain

**Climatic conditions:**

Temperature (°C)	Min: 15°C Max: 35°C
Relative humidity (%)	Max: 75%

**Responsible:**

Fernando Lobo

**Used instruments:**

Measurement instruments	
X	SW
	<ul style="list-style-type: none"> <li>✓ SW CURRENT PRIME audition v1.2.3ct</li> <li>✓ SW PRIME Service Node MAC layer application</li> <li>✓ SW DLMS Simulator 2.2.5 Beta 8 (DNV GL Software)</li> </ul>
X	HW
	<ul style="list-style-type: none"> <li>✓ HW CURRET Base Node</li> <li>✓ HW CURRET Service Node 1</li> <li>✓ HW CURRET Service Node 2</li> <li>✓ HW CURRET Sniffer</li> </ul>
Data registers storage place	
PBNCTT laptop	



## Results:

### 1. PHY layer

#### 1.1. Test setup

The network setup for these tests consists on the following modules:

- PRIME sniffer module, connected in the first level of the network
- Conformance Tester, a laptop with software to control sniffer, the auxiliary service nodes and reference base node with functionality to report the result
- Isolation transformer: Class 1 Construction, 3.0 KVA
- PRIME LISN: Output impedance 0.5 Ω

#### 1.2. Test results

CODE	DESCRIPTION	RESULT	EXPECTED	STAT.	COMMENTS
<b>2.2 PHY Test Cases: Functional Category</b>					
2.2.1	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec and output level 120 dBuV, PPDU length 256 bytes. D8PSK	2000	1996-2000	PASS	1, 2, 3, 4
2.2.2	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec and output level 120 dBuV, PPDU length 256 bytes. D8PSK+CC	2000	1996-2000	PASS	1, 2, 3, 4
2.2.3	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec and output level 120 dBuV, PPDU length 256 bytes. DBPSK	2000	1996-2000	PASS	1, 2, 3, 4
2.2.4	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec and output level 120dBuV, PPDU length 256 bytes. DBPSK+CC	2000	1996-2000	PASS	1, 2, 3, 4
2.2.5	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec and output level 120 dBuV, PPDU length 256 bytes. Modulation type: DQPSK	2000	1996-2000	PASS	1, 2, 3, 4

2.2.6	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec and output level 120 dBuV, PPDU length 256 bytes. DQPSK+CC	2000	1996-2000	PASS	1, 2, 3, 4
2.2.7	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec (20hm) and output level 120 dBuV, PPDU length 256 bytes.DBPSK	2000	1996-2000	PASS	1, 2, 3, 4
2.2.8	Verify error free communication (0.2% FER) checking the complete frame payload when communicating directly over the LISN stated in the PRIME PHY Spec (20hm) and output level 120 dBuV, PPDU length 256 bytes. D8PSK+CC	2000	1996-2000	PASS	1, 2, 3, 4
2.2.9	Verify error free communication (0.2% FER) (checking the complete frame payload) when receiving input signal of 122 dBuV. (DUT is in reception state). Modulation type: D8PSK	2000	1996-2000	PASS	1, 2, 3, 4
<b>2.4 PHY Test Cases: Signal Quality category</b>					
2.4.1	Verify that the EVM of the received signal at output level of 120 dBuV is above 17dB.	18,00 dB	>17 dB	PASS	1, 2, 3, 4
2.4.2	Verify that the EVM of the transmitted signal output level of 120 dBuV is above 17dB.	18,00 dB	>17 dB	PASS	1, 2, 3, 4

**PHY Test Cases: Regulatory category**

- Test report identification

MA109H Service Node Meter is conformant to EN 50065-1, EN 50065-2-3 and EN 50065-7 according verification tests No. 21E040C-01 issued by Laceyca (04/11/2021).

- DUT identification

Model Tested MA109H Service Node Meter with Serial Number:

- 2140000001
- 2140000002
- 2140000003

## 2. MAC layer

### 2.1. Test setup

The network setup for these tests consists on the following modules:

- PRIME sniffer module, connected in level 0 of the network (\*)
- Conformance Tester, a laptop with software to control sniffer, the auxiliary service nodes and reference base node with functionality to report the result
- Isolation transformer: Class 1 Construction, 3.0 KVA
- Attenuators

(\*) Especial test cases:

- Test cases 3.4.3: PRIME sniffer module is connected in level 1 of the network
- Test cases 3.4.8: PRIME sniffer module is connected in level 2 of the network
- Test cases 3.4.9: PRIME sniffer module is connected in level 3 of the network

### 2.2. Test results

CODE	DESCRIPTION	RESULT	EXPECTED	STAT.	COMMENTS
<b>3.2 MAC Test cases: Service Node Start-up</b>					
3.2.1	Service node start-up (forcing the reception of beacons).			PASS	
3.2.2	Service node start-up (No PNPDU are transmit when DUT receives BPDUs).			PASS	
3.2.3	Service node start-up (Tx rate of PNPDU reduced by factor of received PNPDU).			PASS	5
3.2.4	Service node start-up (PNPDU generation latency and transmission parameters).			PASS	5
3.2.5	Service Node start-up (RANDOMness in the transmission of PNPDU)			PASS	
3.2.6	Service Node start-up (seeking promotion of DUT).			PASS	
<b>3.3 MAC Test Cases: Channel Access</b>					
3.3.1	Channel access- Shared Contention Period. Channel is idle			PASS	6
3.3.2	Channel access- Shared Contention Period. Channel is occupied.	MacCSMAChB usyCount = 74 MacCSMAFail Count = 0	MacCSMAFail Count < MacCSMAChB usyCount	PASS	5, 6

3.3.3	Channel access- Contention Free Period.	PASS	6
3.3.4	Channel access- Adaptation to frame structure change (FRA)	PASS	6
<b>3.4 MAC Test Cases: Service Node MAC specific procedures</b>			
3.4.1	Registration accepted (Base Node available when DUT powers up).	PASS	
3.4.2	Registration accepted (Base Node not available when DUT powers up).	PASS	
3.4.3	Registration accepted (DUT connected to a Switch node and the Switch node is connected to the Base Node).	PASS	
3.4.4	Unregistering process initiated by a terminal node.	PASS	7
3.4.5	Unregistering process initiated by the Base node.	PASS	
3.4.6	Promotion process initiated by the base node.	PASS	
3.4.7	Promotion process initiated by the service node DUT.	PASS	
3.4.8	Switching process: 2 levels of switching (DUT1 as a level 1 switch).	PASS	
3.4.9	Switching process: 2 levels of switching (DUT as a level 2 switch).	PASS	
3.4.10	Switching functions: BPDU transmission	PASS	
3.4.11	Switching functions: BPDU updates from FRA control packet	PASS	
3.4.12	Promotion rejected by the base node.	PASS	
3.4.13	Demotion process initiated by the base node.	PASS	

3.4.14	Keep-Alive process (response from DUT).	PASS	
3.4.15	Keep-Alive process (timeout and disconnect).	PASS	
3.4.16	Keep-Alive process (changes in Keep Alive timeout).	PASS	
3.4.17	Connection establishment initiated by the Base node.	PASS	
3.4.18	Connection establishment initiated by the Service node.	PASS	
3.4.19	Connection establishment rejected by the Base node.	PASS	
3.4.20	Connection closing initiated by the Base node.	PASS	
3.4.21	Connection closing initiated by the Service node.	PASS	7
3.4.22	File transfer process (unicast).	PASS	
3.4.23	File transfer process (multicast).	PASS	
3.4.24	Error in the firmware upgrade process.	PASS	

**3. CL layer**

**3.1. Test setup**

The network setup for these tests consists on the following modules:

- PRIME sniffer module, connected in the first level of the network
- Conformance Tester, a laptop with software to control sniffer, the auxiliary service nodes and reference base node with functionality to report the result
- Isolation transformer: Class 1 Construction, 3.0 KVA

**3.2. Test results**

CODE	DESCRIPTION	RESULT	EXPECTED	STAT.	COMMENTS
<b>4.2 CS Test Cases: 4-32 Connection establishment</b>					
4.2.1	Correct establishment and disconnection of 4-32 link			PASS	
<b>4.3 CS Test Cases: DLMS traffic over 4-32 connection</b>					
4.3.1	CS4-32 is able to pass valid DLMS payload between the meter and the test system.			PASS	8

## COMMENTS ON TEST RESULTS

1. All Physical tests were done with AUX1 as transmitting device; except in the test 2.4.2, where the device was configured as receiving. Additionally, the extended power range capability required for test case 2.2.9 is only available in this hardware module.

The bit-to-bit check on the content of the bursts was verified by starting the sniffer via *CURRENT PRIME audition Test Tool* and by means of visual inspection. Only bursts with the content "PRIME IS A WONDERFUL TECHNOLOGY" were sniffed.

2. PrimeGUI 1.3.6 Rev 3736 was used for configuring the DUT in *PHY v1.3.6* mode for transmitting or receiving frames with different modulation type in PHY test cases.
3. PrimeGUI 1.3.6 Rev 3736 was used for reading the PIB attributes *phyStatsRxTotalCount* (0x00A4) and *phyStatsBlkAvgEvm* (0x00A5) from the DUT. The EVM was calculated according to the arithmetic average method based on the value of *phyStatsBlkAvgEvm*.
4. The client indicates that this is a single-phase meter with PRIME signal. Therefore, only the results obtained in the R phase are included.
5. PrimeGUI 1.3.6 Rev 3736 was used for reading the following PIB attributes from the DUT: *macMaxPromotionPdu* (0x0011), *macPromotionPduTxPeriod* (0x0012), *MacMinSwitchSearchTime* (0x0010), *MacCSMAFailCount* (0x0044) and *MacCSMAChBusyCount* (0x0045).
6. For executing MAC test cases related to Channel Access, it was necessary to configure the DUT in 'AppEmu mode' (AppEmu is activated to simulate a real DLMS/COSEM situation and the associated PRIME packets). This configuration was done via PrimeGUI 1.3.6 Rev 3736.
7. To force DUT unregistering process initiated by the DUT, PrimeGUI 1.3.6 Rev 3736 was used for setting PIB attribute *MACActionUnregister* (0x0064). Likewise, PrimeGUI 1.3.6 Rev 3736 was used to force DUT disconnection process initiated by the DUT by setting PIB attribute *MACActionConnClose* (0x0061).
8. The CS test case 4.3.1 related to DLMS traffic over 4-32 connection was performed with DNV GL DLMS Simulator 2.2.5 Beta 8 to force DLMS requests over PRIME PLC for reading some parameters.